

STATE JOB #- - - -

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT NUMBER - R0018

ECMS002 DTGECM03 ECMR003 PAGE 1  
 RUN DATE - 05/14/10  
 RUN TIME - 193048 Revised 06/09/10

COUNTY NAME	CODE	DIST	AIRPORT NAME	FED PROJECT	ILL PROJECT
WINNEBAGO	201	02	CHICAGO ROCKFORD INTERNATIONAL	3-17-0088-XX	RF-D -4008

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR108108	1/C #8 5 KV UG CABLE	L.F.	13,600.000	X	=		
AR108158	1/C #8 5 KV UG CABLE IN UD	L.F.	7,690.000	X	=		
AR1088-12	12 PAIR CONTROL CABLE	L.F.	1,400.000	X	=		
AR109210	VAULT MODIFICATIONS	L.S.	1.000	X	=		
AR110212	2" STEEL DUCT, DIRECT BURY	L.F.	6,430.000	X	=		
AR110213	3" STEEL DUCT, DIRECT BURY	L.F.	200.000	X	=		
AR110504	4-WAY CONCRETE ENCASED DUCT	L.F.	190.000	X	=		
AR110554	EXTEND 4-WAY DUCT	L.F.	280.000	X	=		
AR110610	ELECTRICAL HANDHOLE	EACH	1.000	X	=		
AR110714	ELECTRICAL MANHOLE 4'	EACH	2.000	X	=		
AR125100	ELEVATED RETROREFLECTIVE MARKER	EACH	15.000	X	=		
AR125415	MITL-BASE MOUNTED	EACH	148.000	X	=		
AR125420	TAXIWAY LIGHT INPAVEMENT	EACH	60.000	X	=		
AR125441	TAXI GUIDANCE SIGN, 1 CHARACTER	EACH	2.000	X	=		
AR125442	TAXI GUIDANCE SIGN, 2 CHARACTER	EACH	5.000	X	=		

CHICAGO ROCKFORD INTERNATIONAL  
WINNEBAGO

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES  
CONTRACT NUMBER - R0018

ECMS002 DTGECM03 ECMR003 PAGE 2  
RUN DATE - 05/14/10  
RUN TIME - 193048 Revised 06/09/10

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR125443	TAXI GUIDANCE SIGN, 3 CHARACTER	EACH	2.000 X		=		
AR125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EACH	2.000 X		=		
AR125445	TAXI GUIDANCE SIGN, 5 CHARACTER	EACH	3.000 X		=		
AR125446	TAXI GUIDANCE SIGN, 6 CHARACTER	EACH	2.000 X		=		
AR125525	HIRL, INPAVEMENT	EACH	3.000 X		=		
AR125565	SPLICE CAN	EACH	4.000 X		=		
AR125902	REMOVE BASE MOUNTED LIGHT	EACH	128.000 X		=		
AR125904	REMOVE TAXI GUIDANCE SIGN	EACH	11.000 X		=		
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1.000 X		=		
AR150515	FIELD LABORATORY	L.S.	1.000 X		=		
AR150520	MOBILIZATION	L.S.	1.000 X		=		
AR150540	HAUL ROUTE	L.S.	1.000 X		=		
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	10,910.000 X		=		
AR152442	OFFSITE BORROW EXCAVATION	C.Y.	1,600.000 X		=		
AR152540	SOIL STABILIZATION FABRIC	S.Y.	25,680.000 X		=		

CHICAGO ROCKFORD INTERNATIONAL  
WINNEBAGO

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES  
CONTRACT NUMBER - R0018

ECMS002 DTGECM03 ECMR003 PAGE 3  
RUN DATE - 05/14/10  
RUN TIME - 193048 Revised 06/09/10

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR156510	SILT FENCE	L.F.	3,284.000 X		=		
AR156512	BALES	EACH	100.000 X		=		
AR161601	TEMPORARY GATE	EACH	1.000 X		=		
AR208515	POROUS GRANULAR EMBANKMENT	C.Y.	2,130.000 X		=		
AR209606	CRUSHED AGG. BASE COURSE - 6"	S.Y.	7,000.000 X		=		
AR209612	CRUSHED AGG. BASE COURSE - 12"	S.Y.	18,825.000 X		=		
AR401610	BITUMINOUS SURFACE COURSE	TON	5,800.000 X		=		
AR401630	BITUMINOUS SURFACE TEST SECTION	EACH	1.000 X		=		
AR401650	BITUMINOUS PAVEMENT MILLING	S.Y.	46,225.000 X		=		
AR403610	BITUMINOUS BASE COURSE	TON	10,850.000 X		=		
AR403630	BITUMINOUS BASE TEST SECTION	EACH	1.000 X		=		
AR501515	15" PCC PAVEMENT	S.Y.	20,350.000 X		=		
AR501530	PCC TEST BATCH	EACH	1.000 X		=		
AR602510	BITUMINOUS PRIME COAT	GAL.	8,925.000 X		=		
AR603510	BITUMINOUS TACK COAT	GAL.	12,040.000 X		=		

CHICAGO ROCKFORD INTERNATIONAL  
WINNEBAGO

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES  
CONTRACT NUMBER - R0018

ECMS002 DTGECM03 ECMR003 PAGE 4  
RUN DATE - 05/14/10  
RUN TIME - 193048 Revised 06/09/10

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	25,450.000 X		=		
AR620525	PAVEMENT MARKING-BLACK BORDER	S.F.	24,890.000 X		=		
AR620900	PAVEMENT MARKING REMOVAL	S.F.	2,200.000 X		=		
AR701512	12" RCP, CLASS IV	L.F.	205.000 X		=		
AR701515	15" RCP, CLASS IV	L.F.	230.000 X		=		
AR701518	18" RCP, CLASS IV	L.F.	330.000 X		=		
AR701524	24" RCP, CLASS IV	L.F.	1,130.000 X		=		
AR701530	30" RCP, CLASS IV	L.F.	455.000 X		=		
AR701900	REMOVE PIPE	L.F.	3,030.000 X		=		
AR705524	4" PERFORATED UNDERDRAIN W/SOCK	L.F.	4200.000 X		=		
AR705900	REMOVE UNDERDRAIN	L.F.	1,700.000 X		=		
AR751412	INLET-TYPE B	EACH	3.000 X		=		
AR751550	MANHOLE 5'	EACH	4.000 X		=		
AR751567	MANHOLE 7'	EACH	2.000 X		=		
AR751900	REMOVE INLET	EACH	6.000 X		=		

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR751903	REMOVE MANHOLE	EACH	14.000 X		=		
AR770704	SANITARY MANHOLE 4'	EACH	5.000 X		=		
AR800813	PREFORMED THERMOPLASTIC PVT MARKI	S.F.	5,785.000 X		=		
AR800815	PORTABLE LIGHTED RUNWAY CLOSURE M	EACH	2.000 X		=		
AR800816	L-804 RGL ELEVATED, BASE MOUNTED	EACH	6.000 X		=		
AR800825	TRAFFIC CONTROL AND PROTECTION	L.S.	1.000 X		=		
AR800826	21" SANITARY SEWER	L.F.	925.000 X		=		
AR800868	SOIL GUARD	S.Y.	48,270.000 X		=		
AR901510	SEEDING	ACRE	10.000 X		=		
				TOTAL		\$	

NOTE:

1. EACH PAY ITEM SHOULD HAVE A UNIT PRICE AND A TOTAL PRICE.
2. THE UNIT PRICE SHALL GOVERN IF NO TOTAL PRICE IS SHOWN OR IF THERE IS A DISCREPANCY BETWEEN THE PRODUCT OF THE UNIT PRICE MULTIPLIED BY THE QUANTITY.
3. IF A UNIT PRICE IS OMITTED, THE TOTAL PRICE WILL BE DIVIDED BY THE QUANTITY IN ORDER TO ESTABLISH A UNIT PRICE.
4. A BID MAY BE DECLARED UNACCEPTABLE IF NEITHER A UNIT PRICE NOR A TOTAL PRICE IS SHOWN.