



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 2, 2021

SUBJECT FAP Route 805 (IL 161)  
Section 125CLV-1  
St. Clair County  
Contract No. 76P02  
Item No. 185, June 11, 2021 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Quantities
2. Revised pages i & ii of the Table of Contents of the Special Provisions
3. Revised page 10 of the Special Provisions
4. Revised sheets 3, 4, 6, 9, and 10 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

MTS

## TABLE OF CONTENTS

LOCATION OF PROJECT .....	3
DESCRIPTION OF PROJECT .....	3
SUBMITTAL OF EEO/LABOR DOCUMENTATION .....	3
HOT-MIX ASPHALT SURFACE REMOVAL W/SKETCH OF ILLINOIS STANDARD W8-I107 .....	5
TRAFFIC CONTROL PLAN .....	8
INSTALLATION OF TEMPORARY CONCRETE BARRIERS AND/OR TEMPORARY BRIDGE RAIL .....	8
CLEANING EXISTING DRAINAGE STRUCTURES .....	10
STATUS OF UTILITIES TO BE ADJUSTED .....	10
TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL) .....	10
STRUCTURAL REPAIR OF CONCRETE .....	11
AUTOMATED FLAGGER ASSISTANCE DEVICES (BDE).....	20
BLENDED FINELY DIVIDED MINERALS (BDE).....	21
COMPENSABLE DELAY COSTS (BDE).....	22
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE).....	25
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) .....	27
DISPOSAL FEES (BDE) .....	35
EMULSIFIED ASPHALTS (BDE).....	36
ENGINEER’S FIELD OFFICE AND LABORATORY (BDE) .....	39
HOT-MIX ASPHALT – BINDER AND SURFACE COURSE (BDE).....	41
HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE).....	48
HOT-MIX ASPHALT – MIXTURE DESIGN VERIFICATION AND PRODUCTION (MODIFIED FOR I-FIT) (BDE).....	51
MOBILIZATION (BDE) .....	54
PORTLAND CEMENT CONCRETE – HAUL TIME (BDE).....	55
PORTLAND CEMENT CONCRETE BRIDGE DECK CURING (BDE).....	56
RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (BDE) .....	57
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE) .....	66
STEEL COST ADJUSTMENT (BDE).....	76
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE) .....	78
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) .....	79
SUBMISSION OF PAYROLL RECORDS (BDE).....	79
SURFACE TESTING OF PAVEMENTS – IRI (BDE) .....	79
TEMPORARY PAVEMENT MARKING (BDE).....	84
TRAFFIC CONTROL DEVICES - CONES (BDE).....	87
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION.....	87
WARM MIX ASPHALT (BDE).....	89

WEEKLY DBE TRUCKING REPORTS (BDE)..... 91  
WORK ZONE TRAFFIC CONTROL DEVICES (BDE) ..... 92  
WORKING DAYS (BDE)..... 93

## **CLEANING EXISTING DRAINAGE STRUCTURES**

Description. All existing pipe culverts, storm sewers, and box culverts shall be considered as drainage structures insofar as the interpretation of this Special Provision is concerned. When specified for payments, the locations of drainage structures to be cleaned are scheduled in the plans.

This work shall consist of removing and cleaning all silt, soil sediments, rocks, broken concrete, or any other foreign material deposited or accumulated on all exposed surfaces and within the specified drainage structures to the satisfaction of the Engineer.

All existing drainage structures which are to be adjusted or reconstructed shall be cleaned according to Article 602.15 of the Standard Specifications. This work will be paid for according to accordance with Article 602.16 of the Standard Specifications.

All other existing drainage structures which are specified to be cleaned on the plans will be cleaned according to Article 602.15 of the Standard Specifications.

Construction Requirements. The Contractor shall dispose of the material from the box culvert to be cleaned according to Article 202.03.

Basis of Payment. This work will be paid for at the contract unit price per each for STORM SEWER TO BE CLEANED and BOX CULVERTS TO BE CLEANED.

## **STATUS OF UTILITIES TO BE ADJUSTED**

### **NO UTILITIES TO BE ADJUSTED**

The above represents the best information of the Department and is only included for the convenience of the bidder. The applicable provisions of Sections 102, 103, and Articles 105.07 and 107.20 of the Standard Specifications for Road and Bridge Construction shall apply.

If any utility adjustment or removal has not been completed when required by the Contractor's operation, the Contractor should notify the Engineer in writing. A request for an extension of time will be considered to the extent the Contractor's operations were affected.

### **TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)**

This work shall be done according to Section 701 of the Standard Specifications, Highway Standard 701321, the Staging Details as shown on the plans, and as directed by the Engineer.

This item shall include all traffic control required for construction of structure number 080-2003, as shown on the construction staging and traffic control plans, except for traffic control and protection paid for separately.

This traffic control and protection will be paid for at the contract unit price per each for TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL).

Revised 6-2-2021