



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 2, 2021

SUBJECT: FAU 369 (Cedar Road)  
Section 08-00138-28-TL  
Will County  
Contract No. 61B89  
Item 217  
June 11, 2021 Letting  
Addendum (A)

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised the Schedule of Prices**
- 2. Revised 1<sup>st</sup> page of the Table of Contents to the Special Provisions**
- 3. Revised page 33 of the Special Provisions**
- 4. Revised sheets 8, 12, 23 and 24 of the Plans**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

## TABLE OF CONTENTS

LOCATION OF PROJECT .....	1
DESCRIPTION OF PROJECT .....	1
COMPLETION DATE PLUS WORKING DAYS .....	1
RESTRICTION ON WORKING DAYS AFTER A COMPLETION DATE.....	2
MAINTENANCE OF ROADWAYS .....	2
AGGREGATE SURFACE COURSE FOR TEMPORARY ACCESS (MODIFIED).....	3
TRAFFIC CONTROL PLAN .....	5
TRAFFIC CONTROL AND PROTECTION (ARTERIALS).....	6
PUBLIC CONVENIENCE AND SAFETY (DIST 1).....	6
TEMPORARY PAVEMENT .....	7
ADJUSTMENTS AND RECONSTRUCTIONS.....	7
AGGREGATE SUBGRADE IMPROVEMENT (D-1) .....	9
COARSE AGGREGATE FOR BACKFILL, TRENCH BACKFILL AND BEDDING (D-1).....	11
ENGINEER'S FIELD OFFICE TYPE A (SPECIAL) .....	12
STATUS OF UTILITIES (D-1).....	14
EMBANKMENT I.....	16
HOT-MIX ASPHALT BINDER AND SURFACE COURSE (D-1).....	18
FRICITION AGGREGATE (D-1) .....	26
HAMBURG WHEEL AND TENSILE STRENGTH RATIO TESTING (D-1).....	30
GROUND TIRE RUBBER (GTR) MODIFIED ASPHALT BINDER (D-1) .....	32
SANITARY MANHOLES TO BE RECONSTRUCTED.....	33
FIRE HYDRANTS TO BE RELOCATED OR ADJUSTED .....	34
VILLAGE OF NEW LENOX WATER MAINS .....	34
STEEL CASING .....	35
PIPE CULVERTS, CLASS D, TYPE 1 .....	36
MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE.....	36
SLIPFORM PAVING (D-1).....	36
AVAILABLE REPORTS .....	37
CONSTRUCTION LAYOUT (WCDOT).....	38

Add the following to the end of Note 1. of article 1030.03 of the Standard Specifications:

“A dedicated storage tank for the Ground Tire Rubber (GTR) modified asphalt binder shall be provided. This tank must be capable of providing continuous mechanical mixing throughout by continuous agitation and recirculation of the asphalt binder to provide a uniform mixture. The tank shall be heated and capable of maintaining the temperature of the asphalt binder at 300 °F to 350 °F (149 °C to 177 °C). The asphalt binder metering systems of dryer drum plants shall be calibrated with the actual GTR modified asphalt binder material with an accuracy of ± 0.40 percent.”

Revise 1030.02(c) of the Standard Specifications to read:

“(c) RAP Materials (Note 5) .....1031”

Add the following note to 1030.02 of the Standard Specifications:

Note 5. When using reclaimed asphalt pavement and/or reclaimed asphalt shingles, the maximum asphalt binder replacement percentage shall be according to the most recent special provision for recycled materials.

**SANITARY MANHOLES TO BE RECONSTRUCTED**

Description: This work shall consist of reconstructing sanitary manholes to match the proposed grade in accordance with the applicable portions of Section 602 of the Standard Specifications and as directed by the Engineer. Cretex internal chimney seals shall be installed.

Method of Measurement: This work will be measured for payment per each.

Basis of payment: This work will be paid for at the contract unit price each for SANITARY MANHOLES TO BE RECONSTRUCTED, which price shall be payment in full for all the labor, materials, and equipment necessary to complete the work.

Revised 6/1/2021