



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

May 26, 2021

SUBJECT: Route FAP 809 (Washington Street)
Section 18-00012-01-SW (Millstadt)
St. Clair County
Contract No. 97716
Item 254
June 11, 2021 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 9 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

Panels shall be installed immediately in fresh concrete and adjusted to grade to ensure 100% surface contact with square edges of panels butted tightly together. The base of the truncated domes shall be set flush with the adjoining concrete surface. The maximum tolerance between panels and the adjoining surface is 1/16 inch. Immediately after placement, the panels shall be checked for slope, elevation and proper grade. The concrete around the panels shall be edged with 1/8-inch radius edger and finished according to the contract specifications.

This work shall be measured and paid for at the contract unit price per SQUARE FOOT for DETECTABLE WARNINGS as specified herein.

DRIVEWAY PAVEMENT REMOVAL

This item of work includes the removal of existing driveway pavement to the limits as shown in the plans. Also included in this work is the removal of existing parking lot pavement as shown in the plans needed to install proposed CONCRETE CURB, TYPE B. Removal limits shall be approximately 1-foot behind the proposed curb to allow for forms to be set.

This work shall be measured and paid for at the contract unit price per SQ YD for DRIVEWAY PAVEMENT REMOVAL and no additional compensation will be allowed.

SIDEWALK REMOVAL

This item of work includes the removal of existing sidewalk to the limits as shown in the plans. Also included in this work is the removal of the existing drainage grates, roof drain pipes, and sump drain pipes located within the sidewalk.

This work shall be measured and paid for at the contract unit price per SQ FT for SIDEWALK REMOVAL and no additional compensation will be allowed.

PIPE HANDRAIL

This item of work shall consist of furnishing all materials, labor and equipment necessary to construct the pipe handrail at the locations shown in the plans. This work shall be in accordance with Section 509 of the Standard Specifications and according to the details shown in the plans.

The pipe handrail shall be brushed aluminum. ~~The color of the finish coat shall be black.~~

The handrail shall be bolted to the proposed concrete per the manufacturer's specifications. Cost of the connection shall be included in this item.

The Contractor shall submit shop drawings of the pipe handrail and connection details to the Engineer for approval.

This work shall be measured and paid for at the contract unit price per FOOT for PIPE HANDRAIL which includes the bolted connections and no additional compensation will be allowed.