

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
VARIOUS	2007-0391	COOK	15	8

CONTRACT: 60D27

LOCATION	COMB. CONC. C & G R&R (LF)	HMA SURF R&R FULL DEPTH (SQ YD)	SIDEWALK 5" R&R (SQ FT) 18" CARRIAGE	SIDEWALK 5" R&R (SQ FT) 5' PARALLEL	DRIVEWAY 8" R&R (SQ FT)	SALT TOLERANT SODDING (SQ YD)	REMARKS
4129 W 57th St	5.0	0.8	7.5	0.0	0.0	0.0	
4117 W. 57th St	0.0	0.0	34.5	0.0	0.0	0.0	Replace Carriage Walk Only
3906 W. 57th St	5.0	0.8	7.5	0.0	0.0	0.0	
3842 W. 57th St	10.0	1.7	0.0	0.0	0.0	1.7	
4129 W. 57th PL	10.0	1.7	9.0	0.0	0.0	0.7	Curb behind Type 1 Structure - Sunken Carriage Walk
4144 W. 57th Pl	10.0	1.7	6.0	0.0	0.0	0.7	
3946 W. 58th St	5.0	0.8	7.5	0.0	0.0	0.0	
3846 W. 58th Pl	10.0	1.7	15.0	0.0	0.0	0.0	
3721 W. 59th PL	12.0	2.0	18.0	0.0	0.0	0.0	Sunken Carriage Walk
3827 61st St.	5.0	0.8	0.0	0.0	0.0	0.8	
4720 W. 61st St	6.0	1.0	0.0	0.0	0.0	1.0	
3800 W. 62nd St	680.0	113.3	0.0	50.0	0.0	111.7	
3744 W. 62nd Pl	20.0	3.3	7.5	0.0	0.0	2.5	Sunken Carriage
6033 W. 63rd PL	5.0	0.8	7.5	0.0	0.0	0.0	26' of sunken carriage walk
6225 W. 64th St	5.0	0.8	0.0	0.0	0.0	0.8	Curb behind Type 1 Structure
6130 W. 64th St	5.0	0.8	7.5	0.0	0.0	0.0	
3708 W. 65th Pl	5.0	0.8	0.0	0.0	0.0	0.8	Adj To Sewer
3712 W. 65th Pl	5.0	0.8	0.0	0.0	0.0	0.8	
3730 W. 65th Pl	7.0	1.2	10.5	0.0	0.0	0.0	
3813 W. 65th Pl	10.0	1.7	0.0	0.0	0.0	1.7	Adj to Sewer
3858 W. 65th St	115.0	19.2	0.0	0.0	18.0	17.5	Side of house on Springfiled
4517 W. 65th St	14.0	2.3	0.0	0.0	21.0	0.0	Depressed Curb
3700 W. 66th St.	6.0	1.0	0.0	0.0	9.0	0.0	Depressed Curb
4505 W. 66th St	5.0	0.8	0.0	0.0	0.0	0.8	
3742 W. 66th PL	6.0	1.0	9.0	0.0	0.0	0.0	Curb behind Type 1 Structure
3845 W. 66th PL	5.0	0.8	7.5	0.0	0.0	0.0	
3858 W. 66th PL	30.0	5.0	25.5	0.0	0.0	2.2	
3801 W. 67th PL	10.0	1.7	0.0	0.0	0.0	1.7	5' near corner/sewer 5' near alley
3839 W. 67th PL	0.0	0.0	22.5	0.0	0.0	0.0	Carriage Only Curb Ok
3845 W. 67th PL	5.0	0.8	7.5	0.0	0.0	0.0	
3810 W. 68th St	10.0	1.7	0.0	0.0	0.0	1.7	
3848 W. 68th St	5.0	0.8	7.5	0.0	0.0	0.0	
3840 W. 68th St	25.0	4.2	37.5	0.0	0.0	0.0	
3830 W. 68th St	9.0	1.5	13.5	0.0	0.0	0.0	
3704 W. 68th St	12.0	2.0	18.0	0.0	0.0	0.0	Curb and Sunken Carriage Walk
3901 W. 68th St	44.0	7.3	0.0	30.0	57.0	0.0	Driveway & Alley Wrap
3900 W. 68th St	41.0	6.8	0.0	30.0	52.5	0.0	Driveway & Alley Wrap
3926 W. 68th St	5.0	0.8	7.5	0.0	0.0	0.0	
3849 W. 68th St.	0.0	0.0	43.5	0.0	0.0	0.0	
3900 W. 68th PL	29.0	4.8	0.0	0.0	43.5	0.0	
3752 W. 69th PL	15.0	2.5	7.5	0.0	0.0	1.7	
3639 W. 69th PL	10.0	1.7	15.0	0.0	0.0	0.0	
3845 W. 69th PL	5.0	0.8	0.0	0.0	0.0	0.8	
3630 W. 70th PL	20.0	3.3	12.0	0.0	0.0	2.0	
3835 W. 70th Pl	10.0	1.7	15.0	0.0	0.0	0.0	
3901 W. 71st St	20.0	3.3	0.0	0.0	0.0	3.3	On Side Of House (Springfield)
4200 W. 82nd St	5.0	0.8	0.0	25.0	0.0	0.0	
<b>SUB-TOTAL</b>	<b>1281.0</b>	<b>213.5</b>	<b>387.0</b>	<b>135.0</b>	<b>201.0</b>	<b>154.8</b>	

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**