

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
VARIOUS	2007-0391	COOK	15	10

CONTRACT: 60D27

PARKWAYS

STREET	FROM	TO	LENGTH	WIDTH *	SIDEWALK 4" (SQ FT)	COMMENTS
Marquette Rd. South Side	Lawndale	Central Pk	508.0	6.6	3,352.8	
Marquette Rd. North Side	Lawndale	Central Pk	500.0	6.3	3,150.0	Include corner
Marquette Rd. South Side	Hamlin	Lawndale	492.0	6.0	2,952.0	Include corner
Marquette Rd. North Side	Hamlin	Lawndale	536.0	6.0	3,216.0	
Marquette Rd. South Side	Springfield	Pulaski	375.0	6.0	2,250.0	Up to east of alley
W.Marquette Rd.	3855 W.Marquette Rd.	N/A	30.0	6.1	183.0	
W.Marquette Rd.	3916 W.Marquette Rd.	N/A	28.0	6.2	173.6	
W.Marquette Rd.	3920 W.Marquette Rd.	N/A	37.0	6.2	229.4	
W.Marquette Rd.	3922 W.Marquette Rd.	N/A	29.0	6.2	179.8	
W.Marquette Rd.	3930 W.Marquette Rd.	N/A	48.0	6.2	297.6	
W.Marquette Rd.	3934 W.Marquette Rd.	N/A	36.0	5.0	180.0	
W.Marquette Rd.	3938 W.Marquette Rd.	N/A	35.0	5.0	175.0	
W.Marquette Rd.	3942 W.Marquette Rd.	N/A	40.0	2.5	100.0	
TOTAL =					16,439.2	

* PARKWAYS ARE DEFINED AS THE AREA BETWEEN BACK OF CURB AND THE SIDEWALK

EARTH EXCAVATION FOR THE PCC SIDEWALK 4" AND REMOVAL OF EXISTING ITEMS SUCH AS PAVER BRICKS ARE INCLUDED IN THE COST OF REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES