

SUMMARY OF QUANTITIES			URBAN 90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT		WILL Y032-1F	DUPAGE Y032-1F	COOK Y032-1F				CODE NO		ITEM	UNIT	WILL Y032-1F	DUPAGE Y032-1F	COOK Y032-1F			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	6.2	2.1	0.7				70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.69	0.23	0.08			
67100100	MOBILIZATION	L SUM	1	0.69	0.23	0.08				20076600 TRAINEES	HOURL	500	500						
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.69	0.23	0.08													
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	0.69	0.23	0.08													
81300960	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 42" X 36" X 12"	EACH	2	2	0	0													
X0326459	HANDHOLE, COMPOSITE CONCRETE, 30" X 48"	EACH	19	19	0	0													
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	34584	31691	2552	341													
X0323898	CLOSED CIRCUIT TELEVISION DOME CAMERA	EACH	39	27	9	3													
X0323914	FIBER OPTIC CABLE SPLICE - LATERAL	EACH	5	5	0	0													
X0323957	FIBER OPTIC CABLE SPLICE - MAINLINE	EACH	1	1	0	0													
X0326460	CLOSED CIRCUIT TELEVISION EQUIPMENT, WIRELESS DISTRIBUTION	EACH	102	34	34	34													
X0326461	CLOSED CIRCUIT TELEVISION EQUIPMENT, FIBER OPTIC DISTRIBUTION	EACH	15	5	5	5													
X0326463	WIRELESS VIDEO DISTRIBUTION SYSTEM	L SUM	1	0.69	0.23	0.08													
X0326465	MODIFICATION OF EXISTING VIDEO DISTRIBUTION SYSTEM	L SUM	1	0.69	0.23	0.08													
X0324794	COMMUNICATIONS SHELTER, 10.0' X 12.0'	EACH	1	1	0	0													
X0326464	CLOSED CIRCUIT TELEVISION CAMERA STRUCTURE, 80 FT. MOUNTING HEIGHT	EACH	39	27	9	3													
X0325040	FIBER OPTIC INNERDUCT 1 1/4" DIA.	FOOT	47740	47740	0	0													
X8050010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	13	10	3	0													
81100705	CONDUIT ATTACHED TO STRUCTURE, 2 1/2" DIA., GALVANIZED STEEL PVC COATED	FOOT	220	220	0	0													
81101005	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., GALVANIZED STEEL PVC COATED	FOOT	275	275	0	0													
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	715	550	165	0													
X8160162	UNIT DUCT, 2-1/C NO. 8, 1/C NO. 10 GROUND, 600V, (EPR-TYPE RHW), 1 1/4" DIA. POLYETHYLENE	FOOT	11803	8228	3135	440													
X8710028	FIBER OPTIC CABLE 6 FIBERS, SINGLE MODE	FOOT	1380	1380	0	0													
X8710035	FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	48740	48740	0	0													
89502200	MODIFY EXISTING CONTROLLER	EACH	26	16	7	3													
81018600	CONDUIT PUSHED, 2 1/2" DIAMETER, GALVANIZED STEEL	FOOT	1364	517	748	99													
81018900	CONDUIT PUSHED, 4" DIAMETER, GALVANIZED STEEL	FOOT	946	946	0	0													
XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	39	27	9	3													
X0326462	BUDGETARY ALLOWANCE FOR TOLLWAY FIBER OPTIC CONNECTION	L SUM	1	0.69	0.23	0.08													