

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		1000 FED. 90% STATE 10%						CODE NO	ITEM		UNIT	1000 FED. 90% STATE 10%				
20200100	EARTH EXCAVATION	CU YD	1235	1235					550A0040	STORM SEWERS, CLASS A, TYPE 1 10"	FOOT	25	25					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	2	2					60107600	PIPE UNDERDRAINS 4"	FOOT	400	400					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1039	1039					60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1					
20800150	TRENCH BACKFILL	CU YD	29	29					60600605	CONCRETE CURB, TYPE B	FOOT	294	294					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	3631	3631					60602800	CONCRETE GUTTER, TYPE B	FOOT	664	664					
25000210	SEEDING, CLASS 2A	ACRE	0.8	0.8					60603300	GUTTER OUTLET	EACH	4	4					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	71	71					* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	12.5	12.5					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	71	71					67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	71	71					67100100	MOBILIZATION	L SUM	1	1					
25100630	EROSION CONTROL BLANKET	SO YD	3800	3800					70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1					
25200200	SUPPLEMENTAL WATERING	UNIT	38	38					70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1060	1060					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	79	79					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	9496	9496					
28000300	TEMPORARY DITCH CHECKS	EACH	16	16					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	430	430					
28000400	PERIMETER EROSION BARRIER	FOOT	3265	3265					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	60	60					
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SO YD	130	130					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	87	87					
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	939	939					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	177	177					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4.3	4.3					* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	154.8	154.8					
40600300	AGGREGATE (PRIME COAT)	TON	21.7	21.7					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9496	9496					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2.7	2.7					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	430	430					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	60	60					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	66	66					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	87	87					
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	120	120					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	186	186					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1250	1250					78300100	PAVEMENT MARKING REMOVAL	SO FT	625	625					
42001300	PROTECTIVE COAT	SO YD	163	163					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	140	140					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	9069	9069					* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	60	60					
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	2567	2567					* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	30	30					
44000300	CURB REMOVAL	FOOT	511	511					* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	1	1					
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SO YD	74	74					* 89501510	RELOCATE EXISTING FLASHING BEACON	EACH	2	2					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	8	8					* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	150	150					
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	1816	1816					* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2	2					
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1														
54010202	PRECAST CONCRETE BOX CULVERT 2' X 2'	FOOT	12	12														
54200430	PIPE CULVERTS, TYPE 1 RCCP 15"	FOOT	501	501														
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	14	14														

* Specialty Items