



CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES			
				J000-2A			
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	67	67			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	18	18			
20200100	EARTH EXCAVATION	CU YD	2,930	2,930			
20200200	ROCK EXCAVATION	CU YD	25	25			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	6,365	6,365			
20400800	FURNISHED EXCAVATION	CU YD	115	115			
20800150	TRENCH BACKFILL	CU YD	355.0	355.0			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	62,415	62,415			
25000210	SEEDING, CLASS 2A	ACRE	8.2	8.2			
25000350	SEEDING, CLASS 7	ACRE	4.1	4.1			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,110	1,110			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1,110	1,110			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,110	1,110			
25100115	MULCH, METHOD 2	ACRE	0.15	0.15			
25100630	EROSION CONTROL BLANKET	SQ YD	52,305	52,305			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2,165	2,165			
28000300	TEMPORARY DITCH CHECKS	EACH	76	76			
28000500	INLET AND PIPE PROTECTION	EACH	27	27			
28000510	INLET FILTERS	EACH	18	18			
28100107	STONE RIPRAP, CLASS A4	SQ. YD.	188	188			
28200200	FILTER FABRIC	SQ. YD.	2,220	2,220			
31102000	SUB-BASE GRANULAR MATERIAL, TYPE C	CU YD	1,092	1,092			
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	3,379	3,379			
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	645	645			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,516	2,516			
40600300	AGGREGATE (PRIME COAT)	TON	51	51			
40600895	CONSTRUCTING TEST STRIP	EACH	2	2			
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	4,615	4,615			
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	75	75			
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	2,466	2,466			
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	497	497			
42000540	PORTLAND CEMENT CONCRETE PAVEMENT 12"	SQ YD	70	70			
42001300	PROTECTIVE COAT	SQ YD	1,802	1,802			
44000100	PAVEMENT REMOVAL	SQ YD	1,015	1,015			
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	20,880	20,880			

• SPECIALTY ITEMS

McDonough Associates Inc.
 Engineers / Architects
 130 East Randolph Street, Chicago, Illinois 60601

FILE NAME = 0160F71-SHT-S0001.dgn	USER NAME = TKluegel	DESIGNED - TRK	REVISED -
		DRAWN - TRK	REVISED -
		CHECKED - DLT	REVISED -
		DATE - 03/20/09	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 1 OF 4 SHEETS STA. TO STA.

F.A.I. RTE. 55	SECTION 99-2HB-2-R	COUNTY WILL	TOTAL SHEETS 171	SHEET NO. 4
FED. ROAD DIST. NO. 1			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 60F71	

Rev.

FINAL