



CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES			
				J000-2A			
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2,288	2,288			
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	22,700	22,700			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	45,831	45,831			
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	6,230	6,230			
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	9,173	9,173			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	915	915			
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	775	775			
* 78100300	REPLACEMENT REFLECTOR	EACH	630	630			
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	2,000	2,000			
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2,080	2,080			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	630	630			
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	117	117			
550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	108	108			
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	528	528			
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	180	180			
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	342	342			
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	179	179			
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4			
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	88	88			
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	5,620	5,620			
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	1,690	1,690			
X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	5	5			
X0324774	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SQ YD	1,370	1,370			
X0324775	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ YD	2,735	2,735			
X0325333	HIGH TENSION CABLE GUARDRAIL TERMINAL	EACH	1	1			
X0325444	TEMPORARY CONCRETE BARRIER (INSTALL ONLY)	FOOT	22,700	22,700			
X0325567	STABILIZED SUB-BASE 4 1/2"	SQ YD	543	543			
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	53,881	53,881			
X0325840	WET REFLECTIVE TEMPORARY TAPE TYPE III, 12 INCH	FOOT	350	350			
X0325876	WET REFLECTIVE TEMPORARY TAPE TYPE III, 8 INCH	FOOT	4,505	4,505			
X0326107	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 5 INCH	FOOT	7,050	7,050			
X0712400	TEMPORARY PAVEMENT	SQ YD	3,487	3,487			
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	6	6			
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1			
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	120	120			

* SPECIALTY ITEMS

* Specialty Items

McDonough Associates Inc.
 Engineers / Architects
 130 East Randolph Street, Chicago, Illinois 60601

FILE NAME = D160F71-SHT-S0003.dgn	USER NAME = TKluegel	DESIGNED - TRK	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 1:50	CHECKED - DLT	REVISED -	55					99-2HD-2-R	WILL	171	6	
PLOT DATE = 3/28/2009	DATE - 03/20/09	REVISED -	SCALE: NONE SHEET NO. 3 OF 4 SHEETS STA. TO STA.			CONTRACT NO. 60F71		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				