

EARTHWORK SCHEDULE I-55

BEGIN STATION	END STATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	POROUS GRANULAR EMBANKMENT, SUBGRADE
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
1006+00.00	1007+00.00	75	175	65	25	40	0
1007+00.00	1008+00.00	19	120	15	0	15	0
1008+00.00	1009+00.00	21	60	20	0	20	0
1009+00.00	1010+00.00	23	60	20	0	20	0
1010+00.00	1011+00.00	23	60	20	0	20	0
1011+00.00	1012+00.00	23	60	20	0	20	0
1012+00.00	1013+00.00	23	60	20	0	20	0
1013+00.00	1014+00.00	23	60	20	0	20	0
1014+00.00	1015+00.00	23	60	20	0	20	0
1015+00.00	1016+00.00	23	60	20	0	20	0
1016+00.00	1017+00.00	23	60	20	0	20	0
1017+00.00	1018+00.00	23	60	20	0	20	0
1018+00.00	1019+00.00	23	30	20	0	20	0
1019+00.00	1020+00.00	23	30	20	0	20	0
1020+00.00	1021+00.00	23	60	20	0	20	0
1021+00.00	1022+00.00	23	60	20	0	20	0
1022+00.00	1023+00.00	23	60	20	0	20	0
1023+00.00	1024+00.00	23	60	20	0	20	0
1024+00.00	1025+00.00	23	60	20	0	20	0
1025+00.00	1026+00.00	23	60	20	0	20	0
1026+00.00	1027+00.00	23	60	20	0	20	0
1027+00.00	1028+00.00	23	60	20	0	20	0
1028+00.00	1029+00.00	23	60	20	0	20	0
1029+00.00	1030+00.00	23	60	20	0	20	0
1030+00.00	1031+00.00	23	60	20	0	20	0
1031+00.00	1032+00.00	23	60	20	0	20	0
1032+00.00	1033+00.00	23	60	20	0	20	0
1033+00.00	1034+00.00	23	60	20	0	20	0
1034+00.00	1035+00.00	23	60	20	0	20	0
1035+00.00	1036+00.00	23	60	20	0	20	0
1036+00.00	1037+00.00	23	60	20	0	20	0
1037+00.00	1038+00.00	23	60	20	0	20	0
1038+00.00	1039+00.00	23	60	20	0	20	0
1039+00.00	1040+00.00	23	60	20	0	20	0
1040+00.00	1041+00.00	23	60	20	0	20	0
1041+00.00	1042+00.00	23	60	20	0	20	0
1042+00.00	1043+00.00	23	60	20	0	20	0
1043+00.00	1044+00.00	23	60	20	0	20	0
1044+00.00	1045+00.00	23	60	20	0	20	0
1045+00.00	1046+00.00	23	60	20	0	20	0
1046+00.00	1047+00.00	23	60	20	0	20	0
1047+00.00	1048+00.00	23	60	20	0	20	0
1048+00.00	1049+00.00	23	60	20	0	20	0
1049+00.00	1050+00.00	23	60	20	0	20	0
1050+00.00	1051+00.00	23	60	20	0	20	0
1051+00.00	1052+00.00	23	65	20	5	15	0
1052+00.00	1053+00.00	23	75	20	10	10	0
1053+00.00	1054+00.00	23	80	20	5	15	0
1054+00.00	1055+00.00	7	20	5	0	5	0
1055+00.00	1056+00.00	16	50	15	0	15	0
1056+00.00	1057+00.00	23	75	20	10	10	0
1057+00.00	1058+00.00	23	75	20	10	10	0
1058+00.00	1059+00.00	23	75	20	10	10	0
1059+00.00	1060+00.00	23	75	20	10	10	0
1060+00.00	1061+00.00	9	30	10	0	10	0
1061+00.00	1062+00.00	14	45	10	5	5	0
1062+00.00	1063+00.00	23	85	20	5	15	0
1063+00.00	1064+00.00	8	25	5	0	5	0
1064+00.00	1065+00.00	15	50	15	5	10	0
1065+00.00	1066+00.00	23	85	20	10	10	0
1066+00.00	1067+00.00	23	80	20	5	15	0
1067+00.00	1068+00.00	23	75	20	5	15	0
1068+00.00	1069+00.00	23	75	20	5	15	0
1069+00.00	1070+00.00	23	75	20	5	15	0
1070+00.00	1070+30.00	23	75	20	5	15	0
1070+30.00	1071+00.00	23	75	20	5	15	0
1071+00.00	1072+00.00	23	75	20	5	15	0
1072+00.00	1073+00.00	23	75	20	5	15	0
1073+00.00	1074+00.00	23	75	20	5	15	0
1074+00.00	1075+00.00	23	75	20	5	15	0
1075+00.00	1075+40.00	23	75	20	5	15	0
1075+40.00	1076+00.00	23	75	20	5	15	0
1076+00.00	1077+00.00	23	75	20	5	15	0
1077+00.00	1077+35.00	23	75	20	5	15	0
1077+35.00	1078+00.00	23	75	20	5	15	0

* ASSUME 15% FOR SHRINKAGE

McDonough Associates Inc.
Engineers / Architects
130 East Randolph Street Chicago, Illinois 60601

FILE NAME =	USER NAME = TK1uegal
D:\B071-SHT-SCHEDULE01.dgn	
PLOT SCALE = 1:50	
PLOT DATE = 3/19/2009	

DESIGNED - TRK	REVISED -
DRAWN - TRK	REVISED -
CHECKED - DLT	REVISED -
DATE - 03/20/09	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE SHEET NO. 1 OF 4 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99-2HB-2-R	WILL	171	10
CONTRACT NO. 60F71				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

FINAL