

EARTHWORK SCHEDULE RAMP D

BEGIN STATION	END STATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	POROUS GRANULAR EMBANKMENT, SUBGRADE
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
4006+00.00	4006+50.00	5	15	5	25	-20	0
4006+50.00	4007+00.00	75	70	65	75	-10	0
4007+00.00	4008+00.00	284	200	240	150	90	0
4008+00.00	4009+00.00	175	130	150	105	45	0
4009+00.00	4010+00.00	30	35	25	55	-30	0
4010+00.00	4010+75.05	0	0	0	0	0	0
SUB TOTAL		569	450	485	410	75	0

EARTHWORK SCHEDULE WEST FRONTAGE ROAD

BEGIN STATION	END STATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	POROUS GRANULAR EMBANKMENT, SUBGRADE
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
6067+00.00	6068+00.00	0	0	0	0	0	0
6068+00.00	6068+15.00	25	10	20	10	10	0
6068+15.00	6069+00.00	4	0	5	0	5	0
6069+00.00	6070+00.00	21	35	20	20	0	0
6070+00.00	6071+00.00	23	80	20	55	-35	0
6071+00.00	6072+00.00	21	65	20	65	-45	0
6072+00.00	6073+00.00	23	40	20	50	-30	0
6073+00.00	6074+00.00	21	15	20	30	-10	0
6074+00.00	6075+00.00	19	0	15	30	-15	0
6075+00.00	6076+00.00	17	0	15	40	-25	0
6076+00.00	6077+00.00	17	0	15	40	-25	0
6077+00.00	6078+00.00	19	0	15	35	-20	0
SUB TOTAL		210	245	185	375	-190	0

EARTHWORK SUMMARY

DESCRIPTION	QUANTITY	UNIT
EARTH EXCAVATION	2,930	CU YD
FURNISHED EXCAVATION	115	CU YD
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	6,365	CU YD
ROCK EXCAVATION	25	CU YD

NOTES:

- ROCK EXCAVATION HAS BEEN INCLUDED FOR THE INSTALLATION OF THE PROPOSED STORM SEWER.
- TOP SOIL REMOVAL IS INCLUDED IN REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL.

* ASSUME 15% FOR SHRINKAGE

McDonough Associates Inc.
Engineers / Architects
180 East Randolph Street, Chicago, Illinois 60601

FILE NAME = D:\68771-SHT-SCHEDULE\03.dgn	USER NAME = TKluogal	DESIGNED - TRK	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN - TRK	REVISED -		SCALE: NONE	SHEET NO. 3 OF 4 SHEETS	STA.	TO STA.	55	99-2HB-2-R	WILL	171	12
		CHECKED - DLT	REVISED -							CONTRACT NO. 60F71			
		DATE - 03/20/09	REVISED -		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT								

FINAL