

EROSION CONTROL SCHEDULE I-55

	25100115	25100630	28000250	28000300	28000500	28000510	66400105	X0323426	X0323973	X0323974	X0324045	X0324774	X0324775	28100107
	MULCH, METHOD 2	EROSION CONTROL BLANKET	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS	INLET AND PIPE PROTECTION	INLET FILTERS	CHAIN LINK FENCE, 4'	SÉDIMENT CONTROL, DRAINAGE STRUCTURE	SEDIMENT CONTROL, SILT FENCE	SEDIMENT CONTROL, SILT FENCE	SEDIMENT CONTROL, STABILIZED CONSTRUCTION	SEDIMENT CONTROL, STABILIZED CONSTRUCTION	SEDIMENT CONTROL, STABILIZED CONSTRUCTION	STONE RIPRAP, CLASS A4
	ACRE	SQ YD	POUND	EACH	EACH	EACH	FOOT	EACH	FOOT	FOOT	EACH	SQ YD	SQ YD	SQ YD
SHEET														
EC-1	-	4,517	187	10	-	3	44	15	-	-	3	969	1,938	-
EC-2	-	9,302	384	18	5	5	741	25	959	288	-	-	-	-
EC-3	-	5,590	231	5	3	-	-	-	201	60	-	-	-	-
EC-4	-	3,711	153	3	-	-	-	-	-	-	-	-	-	43
EC-5	-	4,543	188	4	3	-	-	-	63	19	-	-	-	-
EC-6	-	6,546	271	7	7	-	-	-	1,283	385	-	-	-	-
EC-7	-	6,792	281	10	2	-	-	-	1,352	406	-	-	-	-
EC-8	-	5,169	214	8	3	3	-	15	894	268	1	182	364	-
EC-9	-	750	31	3	-	-	-	-	350	105	-	-	-	-
EC-10	-	626	26	1	1	5	-	25	-	-	-	90	179	-
SUB-TOTAL	-	47,550	1,965	69	24	16	785	80	5,105	1,535	4	1,245	2,485	45
AT THE ENGINEER'S DISCRETION	0.15	4,755	200	7	3	2	80	8	515	155	1	125	250	5
GRAND TOTAL	0.15	52,305	2,165	76	27	18	865	88	5,620	1,690	5	1,370	2,735	50

	28200200
	FILTER FABRIC
	SQ YD
SHEET	
EC-1	-
EC-2	-
EC-3	-
EC-4	43
EC-5	-
EC-6	-
EC-7	-
EC-8	-
EC-9	-
EC-10	-
SUB-TOTAL	45
AT THE ENGINEER'S DISCRETION	5
GRAND TOTAL	50

FILE NAME = D:\60F71-SHT-SCHEDULE04.dgn	USER NAME = jletour	DESIGNED - TRK	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>	F.A.I. RTE. 55	SECTION 99-2HB-2-R	COUNTY WILL	TOTAL SHEETS 171	SHEET NO. 13
PLOT SCALE = 1:50	CHECKED - DLT	REVISED -	SCALE: NONE			SHEET NO. 4 OF 4 SHEETS	STA. TO STA.	CONTRACT NO. 60F71		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT
PLOT DATE = 4/14/2009	DATE - 03/20/09	REVISED -								