

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		COOK COUNTY 1000	LAKE COUNTY 1000					CODE NO	ITEM		UNIT				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2	2													
40600300	AGGREGATE (PRIME COAT)	TON	6	6													
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	9	9													
40600895	CONSTRUCTING TEST STRIP	EACH	1	0.8	0.2												
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	146	146													
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	325	325													
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	2901	2901													
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SO YD	170	128	42												
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	110	88	22												
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	58	58													
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	651	134	517												
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	4	2												
67100100	MOBILIZATION	L SUM	1	0.8	0.2												
70300530	PAVEMENT MARKING TAPE, TYPE III 5"	FOOT	191	52	139												
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	80	22	58												
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	14790	10352	4438												
* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	191	52	139												
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	30	10	20												
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	30	10	20												
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.8	0.2												
* SPECIALTY ITEM																	