ROUTE: Cumberland Clover Ramp (NW Exit to off of Kennedy) - HMA SURFACE

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
CUMBERLAND CLOVER RAMP	(NW Exit from Kennedy)	WB	RAMP	2	18	36.0	4
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	8	20	160.0	18
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	4	18	72.0	8
"	"	WB	RAMP	2	200	400.0	44
CUMBERLAND CLOVER RAMP	(NW Exit from Kennedy)	WB	RAMP	12	175	2100.0	233
		TOTALS:			1079 FT		596 SY

ROUTE: SB CUMBERLAND LONG ARM (NW Kennedy Entrance) - HMA SURFACE

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
SB CUMBERLAND LONG ARM	(NW Kennedy Entrance)	WB	RAMP	200	6	1200.0	133.3
"	"	WB	RAMP	25	6	150.0	16.7
"	"	WB	RAMP	40	6	240.0	26.7
"	"	WB	RAMP	20	8	160.0	17.8
"	"	WB	RAMP	70	6	420.0	46.7
"	"	WB	RAMP	14	7	98.0	10.9
"	"	WB	RAMP	30	12	360.0	40.0
"	"	WB	RAMP	12	6	72.0	8.0
"	"	WB	RAMP	12	4	48.0	5.3
"	"	WB	RAMP	12	4	48.0	5.3
"	"	WB	RAMP	12	6	72.0	8.0
"	"	WB	RAMP	12	6	72.0	8.0
"	"	WB	RAMP	4	12	48.0	5.3
"	"	WB	RAMP	4	12	48.0	5.3
"	"	WB	RAMP	4	2	8.0	0.9
"	"	WB	RAMP	4	12	48.0	5.3
"	"	WB	RAMP	4	12	48.0	5.3
"	"	WB	RAMP	4	12	48.0	5.3
"	"	WB	RAMP	4	12	48.0	5.3
"	"	WB	RAMP	4	2	8.0	0.9
"	"	WB	RAMP	4	12	48.0	5.3
"	"	WB	RAMP	4	12	48.0	5.3
"	"	WB	RAMP	4	20	80.0	8.9
"	"	WB	RAMP	4	20	80.0	8.9
"	"	WB	RAMP	100	4	400.0	44.4
		TOTALS:			221 FT		433 SY

FILE NAME = c:\pw_work\PWIDOT\WILGREENDP\d0125109\Design.dgn	USER NAME = WILGREENDP	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/19/2009	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
I-90 (KENNEDY EXPY.)

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2009-029 PP	COOK & LAKE	19	7

CONTRACT NO. 60C28

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

Design.dgn 3/19/2009 8:06:47 AM User=WILGREENDP