

**SUMMARY OF QUANTITIES**

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN	
			100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE I000-2A
20201006	GRADING AND SHAPING SHOULDERS	UNIT	310	310
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	38	38
40600300	AGGREGATE (PRIME COAT)	TON	188	188
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	27	27
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1314	1314
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1277	1277
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7889	7889
42001300	PROTECTIVE COAT	SQ YD	100	100
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	93917	93917
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	500	500
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	5700	5700
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	500	500
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	2800	2800
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	1200	1200
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	1200	1200
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1240	1240
55039700	STORM SEWERS TO BE CLEANED	FOOT	1000	1000
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	30	30
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	164	164
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
* 70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
* 70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
* 70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1
* 70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
* 70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3,271	3,271
* 70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	932	932
* 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	58,333	58,333
* 70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4,148	4,148
* 70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2,194	2,194
* 70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	908	908

\* SPECIALTY ITEM

**SUMMARY OF QUANTITIES**

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN	
			100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE I000
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,091	1,091
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	932	932
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	58,333	58,333
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4,148	4,148
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,194	2,194
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	908	908
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	291	291
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	260	260
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	3,462	3,462
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3945	3945
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	75	75
Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	5	5

\* SPECIALTY ITEM

PLOT DATE = 4/16/2009  
 PLOT SCALE = 1/50  
 USER NAME = JTFreese  
 MODEL = Default



Excellence through Ownership

200 West Front Street  
Wheaton, IL 60187

DESIGNED - MAK	REVISED - ---
DRAWN - JMT	REVISED - ---
CHECKED - BLB	REVISED - ---
DATE - 4/16/2009 1:31:20 PM	REVISED - ---

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**LAKE COOK ROAD**

**SUMMARY OF  
QUANTITIES**

F.A.P. RTE. 1270	SECTION 0506 RS-12	COUNTY LAKE	TOTAL SHEETS 30	SHEET NO. 3
CONTRACT NO. 60H02				
FED. ROAD DIST. NO. 1   ILLINOIS   FED. AID PROJECT				

SCALE: SHEET NO. \_\_\_ OF 30 SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_