



NOTES:

1. USE BLACK LETTERING ON ORANGE BACKGROUND.
2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
3. ERECT SIGN ① WITH INSTALLED PANEL ② ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
4. REMOVE PANEL ② SOON AFTER THE START OF CONSTRUCTION.
5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

ARTERIAL ROAD INFORMATION SIGN

<p>CONSULTING ENGINEERS 1560 WALL ST, SUITE 222 NAPERVILLE, ILLINOIS 60563 PH: 630/577-9100</p>	USER NAME = #USER#	DESIGNED - MJY		STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	DISTRICT ONE DETAIL SHEETS W 119TH STREET			F.A.U. RTE. 1585	SECTION 048 RS	COUNTY COOK	TOTAL SHEETS 18	SHEET NO. 17
	PLOT SCALE = #SCALE#	CHECKED - MJY	REVISED -		SCALE: NONE	SHEET NO. 17 OF 18 SHEETS	STA. 61+00 TO STA. 100+00	D-91-574-09		CONTRACT NO. 60H18		
PLOT DATE = #DATE#	DATE - 04/15/2009	REVISED -					FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT			