CONTRACT NO. 62700

F.A. ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
866	*	LAKE	554	6
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*(L-2[W,R];6,6A & 6 EXT) WRS-1

SUMMARY OF QUANTITIES

URBAN 1001. FED.

PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	1000-2A QUANTITY	
542A5491	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36"	FOOT	463	463	
542A5497	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 42"	FOOT	31	31	
542A5503	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 48"	FOOT	90	90	
542A8245	PIPE CULVERTS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 60"	FOOT	77	77	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	12	12	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2	2	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	8	8	
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2	2	
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1	
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	2	2	
54214509	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 24"	EACH	1	1	
54214515	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	7	7	
54214527	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 42"	EACH	2	2	
54214533	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 48"	EACH	6	6	
54214545	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 60"	EACH	2	2	
54215550	METAL END SECTIONS 15"	EACH	44	44	
54215793	METAL END SECTIONS, EQUIVALENT ROUND - SIZE 48"	EACH	1	1	
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	13	13	
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	8	8	
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	2	2	
54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	1	1	
54247190	GRATING FOR CONCRETE FLARED END SECTION 48"	EACH	2	2	
54248130	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 24"	EACH	1	1	
54248150	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 30"	EACH	7	7	
54248170	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 42"	EACH	2	2	
54248180	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 48"	EACH	6	6	
54248200	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 60"	EACH	2	2	
54248510	CONCRETE COLLAR	CU YD	14	14	
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	788	788	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	5,242	5,242	
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	1,609	1,609	

• DENOTED SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 83
FROM THE WISCONSIN STATE LINE TO
NORTH OF PETITE LAKE ROAD

SUMMARY OF QUANTITIES

SHEET 3 OF 10

DRAWN BY: GP
DATE: 1/30/09 CHECKED BY: MW

GRAEF ANHALT SCHLOEMER & ASSOCIATES, INC.
CHICAGO, ILLINOIS

G:\20004024_N\ms\planset\sumquan03.dgn
5/4/2009 10:39:59 AM