CONTRACT NO. 62700

F.A. ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
866	*	LAKE	554	252
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*(L-2(W,R);6,6A & 6 EXT) WRS-1

THE LAYOUT OF THE RAISED REFLECTIVE PAVEMENT MARKERS WILL BE ACCORDING TO DISTRICT ONE STANDARD NO. TC-20 - TYPICAL APPLICATIONS OF DUAL-DIRECTIONAL SNOWPLOWABLE RAISED PAVEMENT MARKERS.

LOCATION	THPL PVT MK LETTER & SYMBOLS WHITE SQ FT	THPL PVT MK LINE 4 WHITE FOOT	THPL PVT MK LINE 4 YELLOW FOOT	THPL PVT MK LINE 4 YELLOW, 2 AT 11" C-C FOOT	THPL PVT MK LINE 4 YELLOW 10' DASH, 30' SKIP FOOT	THPL PVT MK LINE 5 WHITE FOOT	THPL PVT MK LINE 6 WHITE FOOT	THPL PVT MK LINE 6 WHITE, 2' DASH, 6' SKIP FOOT	THPL PVT MK LINE 8 WHITE FOOT	THPL PVT MK LINE 12 WHITE FOOT	THPL PVT MK LINE 12 YELLOW FOOT	THPL PVT MK LINE 24 WHITE FOOT	RAISED REFL PAVT MKR TWO-WAY AMBER EACH	RAISED REFL PAVT MKR ONE-WAY AMBER EACH	RAISED REFL PAVT MKR ONE-WAY CRYSTAL EACH	RAISED REFL PAVY MKR TWO-WAY BLUE EACH
IL ROUTE 83																
191+85 TO 202+00	0.0	2030.0	0.0	1015.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	26	0	0	0
202+00 TO 226+00	72.8	4559.5	0.0	2158.3	0.0	0.0	300.0	0.0	0.0	0.0	0.0	0.0	54	0	6	0
226+00 TO 250+00	109.2	3035.0	0.0	5169.5	0.0	0.0	384.0	38.0	0.0	0.0	415.2	33.3	42	44	10	0
250+00 TO 274+00	301.6	1876.4	3000.8	2628.8	760.0	0.0	543.1	72.0	0.0	0.0	284.5	41.6	86	28	13	0
274+00 TO 298+00	254.8	3009.2	4085.2	903.9	1020.0	0.0	115.0	0.0	0.0	0.0	108.1	0.0	104	11	3	0
298+00 TO 322+00	291.2	1916.4	3356.4	1773.5	840.0	0.0	230.0	0.0	0.0	0.0	175.8	0.0	95	25	6	8
322+00 TO 408+00	327.6	0.0	0.0	6279.5	0.0	0.0	1153.4	122.0	158.2	59.5	469.4	103.7	43	54	29	6
408+00 TO 431+50	374.4	1650.2	1507.6	4106.0	380.0	0.0	831.5	0.0	0.0	447.3	194.3	46.1	54	49	17	9
431+50 TO 456+00	343.2	0.0	1912.0	3070.4	500.0	0.0	504.1	46.0	0.0	432.0	273.5	65.3	76	33	21	6
456+00 TO 480+00	294.0	2296.5	714.2	3669.7	331.0	0.0	463.5	50.0	0.0	144.0	328.6	228.0	40	43	10	7
480+00 TO 493+17	0.0	2205.0	0.0	0.0	328.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	16	0	0	4
APOLLO COURT	0.0	279.8	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	0	0
WALL STREET	0.0	252.8	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	0	0
TOWN LINE ROAD	0.0	104.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	0	0
GRASS LAKE ROAD	340.8	0.0	0.0	3136.2	0.0	2216.0	1160.3	94.0	0.0	112.9	226.9	204.9	12	35	19	0
EAGLE'S NEST ROAD	0.0	89.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	0	0
GRIMM ROAD	0.0	91.2	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	0	0
IL ROUTE 173	268.0	0.0	0.0	4318.0	0.0	0.0	832.1	144.0	0.0	0.0	392.3	268.6	18	47	17	8
HARDEN STREET	0.0	0.0	0.0	0.0	0.0	0.0	63.3	0.0	0.0	0.0	0.0	12.3	0	0	0	0
CHESTNUT STREET	0.0	63.4	0.0	125.3	0.0	0.0	82.8	0.0	0.0	0.0	0.0	17.9	4	0	2	1
IDA AVENUE	0.0	0.0	0.0	0.0	0.0	0.0	68.9	0.0	0.0	0.0	0.0	13.5	0	0	0	0
WILTON DRIVE	0.0	0.0	0.0	0.0	0.0	0.0	86.2	0.0	0.0	0.0	0.0	12.9	0	0	0	0
PARK STREET	0.0	0.0	0.0	0.0	0.0	0.0	111.6	0.0	0.0	0.0	0.0	0.0	0	0	0	0
LAKE STREET	0.0	122.0	0.0	241.1	0.0	0.0	118.7	0.0	0.0	0.0	0.0	27.2	6	0	3	1
ORCHARD STREET	0.0	0.0	0.0	0.0	0.0	0.0	270.6	0.0	0.0	0.0	0.0	57.9	0	0	0	0
DEPOT STREET	0.0	0.0	0.0	68.3	0.0	0.0	96.7	0.0	0.0	0.0	0.0	15.8	4	3	0	0
WILLIAMS STREET	0.0	0.0	0.0	0.0	0.0	0.0	68.9	0.0	0.0	0.0	0.0	0.0	0	0	0	0
POPLAR AVENUE	0.0	0.0	0.0	0.0	0.0	0.0	74.4	0.0	0.0	0.0	0.0	0.0	0	0	0	0
FIRST STREET	0.0	0.0	0.0	0.0	0.0	0.0	74.4	0.0	0.0	0.0	0.0	0.0	0	0	0	0
SECOND STREET	0.0	0.0	0.0	0.0	0.0	0.0	78.0	0.0	0.0	0.0	0.0	0.0	0	0	0	0
NORTH AVENUE	231.6	0.0	0.0	2918.0	0.0	0.0	451.9	56.0	0.0	184.0	180.1	251.2	16	30	11	3
KAIRY'S STREET	0.0	168.9	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	0	0	0
SUB-TOTAL	**3,209**	**23,750**	**14,576**	**41,581**	**4,159**	**2,216**	**8,163**	**622**	**158**	**1,380**	**3,049**	**1,400**	**696**	**402**	**167**	**53**

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 83
FROM THE WISCONSIN STATE LINE TO
NORTH OF PETITE LAKE ROAD

PAVEMENT MARKING SCHEDULE

DRAWN BY: TMM
DATE: 1/30/09 CHECKED BY: RS

GRAEF, ANHALT, SCHLOEMER & ASSOCIATES, INC.
CHICAGO, ILLINOIS

G:\2004024.N\ms\pionset\pmkgschedule.dgn
1/27/2009
9:32:15 AM