

La Grange Rd. @ 57th St., 58th St. & 59th St.

Special Provision	ITEM #	CODE NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY Y003	CONTRACT 1 ITEM	CONTRACT 2 ITEM	CONTRACT 3 ITEM	CONTRACT 4 ITEM	CONTRACT 5 ITEM	CONTRACT 6 ITEM	57th St. S.W. QUAD.	57th St. S.E. QUAD.	57th St. N.W. QUAD.	57th St. N.E. QUAD.	58th St. WEST	58th St. S.E. QUAD.	58th St. N.E. QUAD.	59th St. N.E. QUAD.	59th St. S.E. QUAD.	59th St. N.W. QUAD.
N	1	20101700	SUPPLEMENTAL WATERING	UNIT	16				X			2	2	2	2	0	2	2	2	2	0
N	2	20200100	EARTH EXCAVATION	CU. YD.	312	X						33.7	36.1	42.9	44.4	57.3	23.8	35.5	18.8	19.1	0
N	3	25000400	NITROGEN FERTILIZER NUTRIENT	LB.	2				X			0.1	0.4	0.1	0.9	0.0	0.0	0.0	0.0	0.0	0
N	4	25000500	PHOSPHOROUS FERTILIZER NUTRIENT	LB.	2				X			0.1	0.4	0.1	0.9	0.0	0.0	0.0	0.0	0.0	0
N	5	25000600	POTASSIUM FERTILIZER NUTRIENT	LB.	2				X			0.1	0.4	0.1	0.9	0.0	0.0	0.0	0.0	0.0	0
N	6	25200110	SODDING SALT TOLERANT	SQ. YD.	144				X			11	39	14	80	0	0	0	0	0.0	0
N	7	21101810	COMPOST FURNISH AND PLACE 3"	SQ. YD.	47				X			0.8	3.3	0.8	2.5	0.0	4.1	3.7	32.1	0.0	0
N	8	35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ. YD.	342				X			30.9	30.7	32.5	33.4	85.1	41.8	58.5	11.2	18.0	0
N	9	40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	6	X						0	0	0	0	0	0	0	0	0	0
N	10	42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5"	SQ. FT.	325		X					0	0	37	166	0	0	0	50	72	0
Y	11	44001005	HOT-MIX ASPHALT SURFACE REMOVAL	SQ. YD.	52.4	X						0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0
N	12	44000100	PAVEMENT REMOVAL	SQ. YD.	277	X						169	0	0	0	108	0	0	0	0	0
N	13	44000300	CURB REMOVAL	FOOT	19	X						0	0	0	0	8	11	0	0	0	0
N	14	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	411	X						62	68	58	58	70	40	55	0	0	0
N	15	44000600	SIDEWALK REMOVAL	SQ. FT.	1637	X						41	63	164	235	387	222	263	131	131	0
N	16	50300225	CONCRETE STRUCTURES	CU YD	46		X										19.1			5.6	
N	17	50800105	REINFORCEMENT BARS	POUND	3130		X										1470.0			410.0	
N	18	60600605	CONCRETE CURB, TYPE B	FOOT	20		X					0	0	0	0	9	11	0	0	0	0
N	19	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	100		X					13	21	14	41	0	11	0	0	0	0
N	20	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	326		X					46	48	47	47	69	29	40	0	0	0
Y	21	60626500	TRANSITIONAL COMBINATION CONCRETE CURB AND GUTTER	FOOT	15		X					0	0	0	0	0	0	15	0	0	0
Y	22	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	X															
N	23	78000400	THERMOPLASTIC PAVEMENT MARKING - 6"	FOOT	357	X								159			197			0	0
N	24	78000650	THERMOPLASTIC PAVEMENT MARKING - 24"	FOOT	101	X								29			71			0	0
N	25	81012200	CONDUIT IN TRENCH, 3/4" DIA. PVC	FOOT	912				X					432			288				192
N	26	81018600	CONDUIT PUSHED, 2 1/2" DIA. GALVANIZED STEEL	FOOT	380				X					190			120				70
N	27	81021390	CONDUIT PUSHED, 6" DIA., PVC	FOOT	424				X					269			155				0
N	28	81021370	CONDUIT PUSHED, 4" DIA., PVC	FOOT	1418				X					269			155				994
Y	29	81603162	UNIT DUCT, 600V, 2-1C NO.6, 1/1C NO. 8 GROUND, (ERP - TYPE RHW), 1 1/4" DIA. POLYETHYLENE	FOOT	780				X					400			200				180
N	30	A2007616	TREE, TAXODIUM DISTICHUM, (COMMON BALD CYPRESS) 2" CALIPER, BALLED AND BURLAPED	EACH	3				X			0	0	0	0	0	0	0	1	2	0
N	31	A2007628	TREE, TAXODIUM DISTICHUM, (COMMON BALD CYPRESS) 3 1/2" CALIPER, BALLED AND BURLAPED	EACH	2				X			0	0	0	0	0	0	0	1	1	0
N	32	B2000564	TREE, AMELANCHIER CANADENSIS (SHADBLow SERVICEBERRY) 5' HEIGHT, SHRUB FORM, BALLED AND BURLAPED	EACH	4				X			1	1	1	1	0	0	0	0	0	0
N	33	C2C01736	SHRUB, CORNUS SERICEA CARDINAL (CARDINAL REDOSIER DOG WOOD) 3" CONTAINER	EACH	7				X			0	0	0	0	0	0	0	3	4	0
N	34	C2011036	SHRUB, SYRINGA PATULA MISS KIM (MISS KIM MANCHURIAN LILAC) 3' HEIGHT BALLED AND BURLAPED	EACH	2				X			1	0	1	0	0	0	0	0	0	0
N	35	D2000636	SHRUB, JUNIPERUS CHINENSIS SEA GREEN (SEA GREEN JUNIPER) 3' WIDTH, BALLED AND BURLAPED	EACH	7				X			2	2	1	2	0	0	0	0	0	0
Y	36	XX005967	TOPSOIL (PLANTING MIXTURE)	CU. YD.	722				X			95.4	120.3	35.1	78.6		35.6	25.2	331.4	0.0	0
Y	37	XX006571	REMOVE AND REPLACE BOLLARDS	EACH	13	X						0	0	0	0	13	0	0	0	0	0
Y	38	XX006834	ELECTRICAL CONNECTION TO EXISTING LIGHTING SYSTEM	EACH	3									1			1				1
Y	39	X0325713	GROUND ROD	EACH	12					X				4			6				2
Y	40	X7240500	RELOCATE EXISTING SIGNS	EACH	4	X						1	0	0	2	0	0	1	0	0	0
Y	41	Z0017400	DRAINAGE AND UTILITY STRUCTURES TO BE ADJUSTED	EACH	3	X						0	0	0	0	2	1	0	0	0	0
Y	42	Z0051500	REMOVING AND RESETTING STREET SIGNS	EACH	1	X						0	0	0	0	0	0	1	0	0	0
Y	43	XX006653	FENCE (SPECIAL)	FOOT	64					X		0.00	0.00	0.00	0.00	0.00	0.00	0.00	64		0
Y	44	XX003056	RAIL REMOVAL	FOOT	32					X		0.0	0.0	0.0	0.0	0.0	0.0	0.0		31.7	0
Y	45	X0321710	GRANULAR SUBBASE	CU. YD.	3				X			0.2	0.2	0.2	1.2	0.7	0.2	0.2	0.0	0.0	0
Y	46	XX008028	#10 WIRE	FOOT	2640					X							810				540
Y	47	LR 430030	CONCRETE PAVER PAVEMENT	SQ. YD.	342				X			29.6	23.4	27.5	29.8	60.7	35.4	46.1	10.0	0.0	14.6
									X			4.8	5.4	5.9	4.9	24.7	5.3	6.4	1.4	0.0	0.8
									X			0.7	0.7	0.7	0.7	0.7	0.7	1.4	0.0	0.0	0
Y	50	XX008029	LIGHTING CONTROL PANEL	EACH	6					X							3				1
Y	51	B1400105	HANDHOLE (SPECIAL)	EACH	2					X							0				0
Y	52	XX008030	M1 - IN-GRADE FIXTURE FOR UPLIGHTING	EACH	26					X							10				4
Y	53	XX008031	M2 - KNUCKLE MOUNT ACCENT FIXTURE	EACH	18					X							4				4
Y	54	XX008032	M3 - FIXTURE IN PYLON	EACH	10					X							4				2
Y	55	XX008033	DUPLEX WEATHERPROOF GFI RECEPTACLE AND COVER PLATE	EACH	16					X							6				3
Y	56	XX008034	SEATWALL 20" HT.	FOOT	104				X			13.5	13.5	13.5	13.5	22.0	10.0	10.0	0.0	8.0	0
Y	57	XX008035	PILLAR 24" HT.	EACH	21				X			3.0	3.0	3.0	3.0	4.0	2.0	2.0	0.0	1.0	0
Y	58	XX008036	PYLON PILLAR 40" HT.	EACH	8				X			1.0	1.0	1.0	1.0	2.0	1.0	1.0	0.0	0.0	0
Y	59	XX008037	PYLON PILLAR 52" HT.	EACH	2				X			0	0	0	0	0	0	0	1	1	0
Y	60	XX008038	PYLON	EACH	10					X		1	1	1	1	2	1	1	1	1	0
Y	61	XX008039	GALVANIZED SPIKE WITH 8" PLASTIC EDGE	FOOT	294				X			15	16	17	12	0	58	58	59	59	0
Y	62	XX008040	SHRUB, JUNIPERUS VIRGINIA 'MANHATTIN BLUE' 5' HIGH	EACH	3				X			1	1	0	1	0	0	0	0	0	0
Y	63	XX008041	PERENNIAL PLANTS, EUONYMUS FORTUNIE VAR. COLORATUS, 1 QUART	EACH	230				X			0	0	0	0	0	0	0	0	230	0
Y	64	XX008042	PERENNIAL PLANTS, HELICTOTRICHON SEMPER VIRENS, 2 GALLON	EACH	64				X			7	7	2	13	0	8	8	0	19	0
Y	65	XX008043	PERENNIAL PLANTS, CALLIRHOE INVOLUCRATA	EACH	69				X			14	6	6	5	0	5	5	0	28	0
Y	66	XX008044	PERENNIAL PLANTS, LONICERA X BROWNII 'DROPMORE SCARLET'	EACH	4				X			0	0	0	0	0	0	0	0	4	0
Y	67	XX008045	PERENNIAL PLANTS, PEROSKIA ATRIPLICIFOLIA 'LITTLE SPIRE'	EACH	16				X			0	0	0	0	0	0	0	0	16	0
Y	68	XX008046	LANDSCAPE RESTORATION (SOD)	EACH	8				X			0	0	1	1	0	1	0	1	1	3
Y	69	XX008047	METAL LETTERING 4"	EACH	22					X		11	0	0	11	0	0	0	0	0	0
Y	70	XX008048	METAL LETTERING 8"	EACH	11					X		0	0	0	0	11	0	0	0	0	0
Y	71	XX008049	HELICAL PIER	EACH	3					X											0

* SPECIALTY ITEMS

FILE NAME = \$FILES\$	USER NAME = \$USER\$	DESIGNED --	REVISED --	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -- ICJ	REVISED --		SCALE:	STA.	TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT			
		CHECKED -- BS	REVISED --										
		DATE -- 4/30/09	REVISED --										

TENG
 TENG & ASSOCIATES, INC.
 ENGINEERS/ARCHITECTS/PLANNERS
 205 N. MICHIGAN AVE. CHICAGO, IL 60601
 TELEPHONE: 312/616-0000

C:\IC-VorkSpace\MURPHY\JTM\F-5-0044.D-Trans_07\2202\20433-001\Comm\CAD\01_Design\LA Teng\Sheet\sc011A01.dwg
 04-30-2009 11:45:41 CREF: Xref\sc011A01.dwg