

EARTH EXCAVATION ---- DUNHAM ROAD

STATION	CUT END AREA (SF)	FILL END AREA (SF)	CUT AVERAGE END AREA (SF)	FILL AVERAGE END AREA (SF)	LENGTH (FT)	EXCAVATION (CUT) VOLUME (CU YD)	EMBANKMENT (FILL) VOLUME (CU YD)
248+50.00	0.84	0.19					
249+00.00	0.43	0.39	0.64	0.29	50.00	1.18	0.54
249+50.00	0.31	1.89	0.37	1.14	50.00	0.69	2.11
249+74.00	45.93	5.71	23.12	3.80	24.00	20.55	3.38
250+00.00	45.56	5.62	45.75	5.67	26.00	44.05	5.46
250+50.00	58.61	1.47	52.09	3.55	50.00	96.45	6.56
251+00.00	39.22	24.28	48.92	12.88	50.00	90.58	23.84
251+50.00	49.39	37.26	44.31	30.77	50.00	82.05	56.98
252+00.00	83.57	34.47	66.48	35.87	50.00	123.11	66.42
252+50.00	84.49	31.64	84.03	33.06	50.00	155.61	61.21
253+00.00	81.80	6.27	83.15	18.96	50.00	153.97	35.10
253+50.00	27.17	41.43	54.49	23.85	50.00	100.90	44.17
254+00.00	29.82	57.43	28.50	49.43	50.00	52.77	91.54
254+50.00	19.53	42.54	24.68	49.99	50.00	45.69	92.56
255+00.00	71.49	28.90	45.51	35.72	50.00	84.28	66.15
255+50.00	110.51	75.56	91.00	52.23	50.00	168.52	96.72
256+00.00	141.53	79.84	126.02	77.70	50.00	233.37	143.89
256+50.00	90.09	70.84	115.81	75.34	50.00	214.46	139.52
257+00.00	104.64	77.58	97.37	74.21	50.00	180.31	137.43
257+50.00	71.93	111.00	88.29	94.29	50.00	163.49	174.61
258+00.00	80.69	152.26	76.31	131.63	50.00	141.31	243.76
258+50.00	68.14	334.20	74.42	243.23	50.00	137.81	450.43
259+00.00	70.28	461.46	69.21	397.83	50.00	128.17	736.72
259+50.00	87.40	457.79	78.84	459.63	50.00	146.00	851.16
260+00.00	106.23	424.77	96.82	441.28	50.00	179.29	817.19
260+50.00	111.08	504.25	108.66	464.51	50.00	201.21	860.20
261+00.00	93.03	104.83	102.06	304.54	50.00	188.99	563.96
261+31.98	71.70	21.28	82.37	63.06	31.98	97.56	74.69
261+50.00	24.14	57.97	47.92	39.63	18.02	31.98	26.45
264+00.00	395.01	340.77					
264+50.00	402.40	480.27	398.71	410.52	50.00	738.34	760.22
265+00.00	277.66	733.83	340.03	607.05	50.00	629.69	1124.17
265+50.00	220.27	1552.65	248.97	1143.24	50.00	461.05	2117.11
266+00.00	126.41	2071.86	173.34	1812.26	50.00	321.00	3356.03
266+50.00	72.73	2131.49	99.57	2101.68	50.00	184.39	3891.99
267+00.00	84.22	1912.25	78.48	2021.87	50.00	145.32	3744.20
267+50.00	187.86	1904.02	136.04	1908.14	50.00	251.93	3533.58
268+00.00	231.81	1848.65	209.84	1876.34	50.00	388.58	3474.69
268+50.00	218.58	1882.37	225.20	1865.51	50.00	417.03	3454.65
269+00.00	259.58	1897.76	239.08	1890.07	50.00	442.74	3500.12
269+50.00	189.90	1998.87	224.74	1948.32	50.00	416.19	3607.99
270+00.00	25.49	2304.83	107.70	2151.85	50.00	199.44	3984.91

EARTH EXCAVATION ---- DUNHAM ROAD

STATION	CUT END AREA (SF)	FILL END AREA (SF)	CUT AVERAGE END AREA (SF)	FILL AVERAGE END AREA (SF)	LENGTH (FT)	EXCAVATION (CUT) VOLUME (CU YD)	EMBANKMENT (FILL) VOLUME (CU YD)
273+50.00	228.66	1861.64					
274+00.00	176.15	1586.83	202.41	1724.24	50.00	374.82	3193.03
274+50.00	134.71	1420.66	155.43	1503.75	50.00	287.83	2784.71
275+00.00	76.16	1725.33	105.44	1573.00	50.00	195.25	2912.95
275+50.00	41.76	1864.57	58.96	1794.95	50.00	109.19	3323.98
275+65.09	7.88	1940.84	24.82	1902.71	15.09	13.87	1063.40
277+08.53	0.00	2416.14					
277+50.00	0.00	2278.67	0.00	2347.41	41.47	0.00	3605.44
278+00.00	400.88	1295.61	200.44	1787.14	50.00	371.19	3309.52
278+50.00	508.05	860.94	454.47	1078.28	50.00	841.60	1996.81
279+00.00	234.96	390.69	371.51	625.82	50.00	687.97	1158.92
279+50.00	120.72	117.39	177.84	254.04	50.00	329.33	470.44
280+00.00	108.18	32.70	114.45	75.05	50.00	211.94	138.97
280+50.00	99.98	31.50	104.08	32.10	50.00	192.74	59.44
281+00.00	61.05	48.74	80.52	40.12	50.00	149.10	74.30
281+50.00	36.77	65.97	48.91	57.36	50.00	90.57	106.21
282+00.00	37.42	74.63	37.10	70.30	50.00	68.69	130.19
282+50.00	18.83	70.67	28.13	72.65	50.00	52.08	134.54
283+00.00	20.79	74.10	19.81	72.39	50.00	36.69	134.05
283+50.00	23.24	28.42	22.02	51.26	50.00	40.77	94.93
284+00.00	43.00	15.16	33.12	21.79	50.00	61.33	40.35
284+50.00	43.06	15.88	43.03	15.52	50.00	79.69	28.74
285+00.00	47.70	16.82	45.38	16.35	50.00	84.04	30.28
285+50.00	57.12	5.40	52.41	11.11	50.00	97.06	20.57
286+00.00	51.54	10.88	54.33	8.14	50.00	100.61	15.07
286+50.00	51.29	3.75	51.42	7.32	50.00	95.21	13.55
287+00.00	51.09	2.23	51.19	2.99	50.00	94.80	5.54
287+50.00	47.64	3.03	49.37	2.63	50.00	91.42	4.87
288+00.00	50.50	0.38	49.07	1.71	50.00	90.87	3.16

EARTH EXCAVATION ---- GILBERT STREET

STATION	CUT END AREA (SF)	FILL END AREA (SF)	CUT AVERAGE END AREA (SF)	FILL AVERAGE END AREA (SF)	LENGTH (FT)	EXCAVATION (CUT) VOLUME (CU YD)	EMBANKMENT (FILL) VOLUME (CU YD)
306+00.00	8.64	0.00					
306+50.00	8.06	1.09	8.35	0.55	50.00	15.46	1.01
307+00.00	34.13	0.56	21.10	0.83	50.00	39.06	1.53
307+50.00	42.18	0.86	38.16	0.71	50.00	70.66	1.31
308+00.00	52.65	0.84	47.42	0.85	50.00	87.81	1.57
308+50.00	54.73	1.18	53.69	1.01	50.00	99.43	1.87
309+00.00	59.70	4.47	57.22	2.83	50.00	105.95	5.23
309+50.00	67.23	10.63	63.47	7.55	50.00	117.53	13.98
310+00.00	64.38	4.53	65.81	7.58	50.00	121.86	14.04
310+50.00	43.20	7.92	53.79	6.23	50.00	99.61	11.53
311+00.00	48.10	0.70	45.65	4.31	50.00	84.54	7.98
311+50.00	43.42	1.02	45.76	0.86	50.00	84.74	1.59

x:\2009\3944\engineer-ing_documents\general\p\p\in_abc_E\schoc_02.dgn