

SIGNING SCHEDULE - GROUND MOUNTED SIGNS										
STATION	OFFSET (LT/RT/)	SIGN NO. (MUTCD)	CLASSIFICATION (CONVENTIONAL / BIKEPATH)	SIZE (INCHES)		AREA (SQ FT)		MESSAGE OR SYMBOL	NO. OF POSTS	TELESCOPING STEEL SIGN SUPPORTS FT
				WIDTH	HEIGHT	TYPE 1	TYPE 2			
KANE / DUPAGE COUNTY FAP 361										
<b>DUPAGE COUNTY SIGNS TO BE FURNISHED AND INSTALLED BY DUPAGE COUNTY (NOT IN CONTRACT)</b>										
II-25/STEARNS RD										
165+15.00	41 LT	M1-6	CONVENTIONAL	36	36	9.00		DUPAGE/29/COUNTY	1	15.7
		M4-8b	CONVENTIONAL	21	15	2.19		END		
		SIGN06	CONVENTIONAL	36	24	6.00		KANE/COUNTY		
166+15.00	38 RT	M1-6	CONVENTIONAL	36	36	9.00		DUPAGE/29/COUNTY	1	15.7
		M4-8b		21	15	2.19		BEGIN		
		SIGN07		36	24	6.00		DUPAGE/COUNTY		
168+00.00	38 RT	W11-3	CONVENTIONAL	30	30	6.25		DEER CROSSING	1	14.0
171+00.00	31 LT	W2-2	CONVENTIONAL	30	30	6.25		3 WAY INTERSECTION	1	13.4
		W7-100	CONVENTIONAL	56	9	3.50		OLD STEARNS RD		
172+50.00	48 LT	SIGN 7A	CONVENTIONAL	45	21	6.56		PROPERTY/OF KANE COUNTY/NO TRESPASS	1	13.6
178+00.00	41 RT	R2-1	CONVENTIONAL	24	30	5.00		SPEED LIMIT 50	1	14.1
181+00.00	47.1 LT	R2-1	CONVENTIONAL	24	30	5.00		SPEED LIMIT 45	1	16.2
188+66.00	56 LT	R3-5	CONVENTIONAL	30	36	7.50		RIGHT TURN ONLY	1	15.3
192+00.00	41 LT	W11-3	CONVENTIONAL	30	30	6.25		DEER CROSSING	1	14.7
192+00.00	42.5 RT	R2-1	CONVENTIONAL	24	30	5.00		SPEED LIMIT 50	1	15.6
						<b>86.00</b>	<b>0.00</b>	<b>TOTAL QUANTITY</b>	<b>10</b>	<b>149.0</b>

x:\3900a\3944\engineering\_documents\pvmnt\_mkg\_sign\pvmnt\_mkg\_sign\ABC\_pmk\ksgsch3.dgn

FILE NAME = #FILES#	USER NAME = #USER#	DESIGNED - JRM	REVISED -	<b>KANE COUNTY DIVISION OF TRANSPORTATION</b>	<b>PAVEMENT MARKING AND SIGNING SCHEDULE</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - VLM	REVISED -			361	06-00214-15-BR	KANE/DUPAGE	545	240
PLOT SCALE = 1.0000" / IN.	CHECKED - JNR	REVISIED -				CONTRACT NO. 63074				
PLOT DATE = 3/30/2009	DATE - 3/31/09	REVISED -				SCALE:	SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	