SUMMARY OF QUANTITIES

ITEM#		CODE#	ITEM	UNIT	QUANTITY (1000-2A)
1		40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4,165
2		40600300	AGGREGATE (PRIME COAT)	TON	91
3		40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	30
4		40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	45
5		40600895	CONSTRUCTING TEST STRIP	EACH	1
6		40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,320
7		40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	4,070
8		44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	40,100
9		44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL & REPLACEMENT	FOOT	150
10		44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	90
11		44212900	PAVEMENT PATCHING (PARTIAL DEPTH)	SQ YD	50
12		60255500	MANHOLES TO BE ADJUSTED	EACH	4
13		60260100	INLETS TO BE ADJUSTED	EACH	2
14		60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1
15		60266600	VALVE BOXES TO BE ADJUSTED	EACH	1
16		67100100	MOBILIZATION	L SUM	1
17		70101700	TRAFIC CONTROL AND PROTECTION	L SUM	1
18		70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1
19		70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1
20		70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
21		70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6,910
22		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	12,300
23	*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	510
24	*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15,500
25	*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	12,200
26	*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	980
27	*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	255
28	*	78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	640
29		78300100	PAVEMENT MARKING REMOVAL	SQ FT	100
30		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	850
31	*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	560
32		X0325866	CENTER LINE - RUMBLE STRIP	FOOT	5,610
33		XX005462	CHANGEABLE MESSAGE SIGN	WEEK	5
34	*	XX006257	RECESSED REFLECTIVE PAVEMENT MARKER	EACH	850
35		XX007831	SAG FRAME AND LID	EACH	1

* DENOTES SPECIALTY ITEM.

FILE NAME = *FILEL*	USER NAME =	DESIGNED - CRC	REVISED - 02/11/2009	**STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION**	**DIEHL ROAD LAPP IMPROVEMENTS SUMMARY OF QUANTITIES**
		DRAWN - CRC	REVISED -		
	PLOT SCALE =	CHECKED - JLC	REVISED -		SCALE: 1" = 100' STA. TO STA.
	PLOT DATE =	DATE - 01/02/2009	REVISED -		

CO. HWY.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
53	08-00263-01SP	DUPAGE	16	2
	SUMMARY OF QUANTITIES	CONTRACT NO: 63122		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		