

EARTHWORK		
LOCATION	REMOVAL & DISPOSAL OF UNSUITABLE MAT.* (CU YD)	FURNISHED EXCAVATION** (CU YD)
RAILWAY/WATER TOWER CAMPUS AREA	415	40
EAST AVE. AND PINE AVE. LANDSCAPE RESTORATION	30	0
EAST AVE. AND PINE AVE. UNDERCUTS	77	0
TOTAL QUANTITY =	522	40

*ALL CUT MATERIAL SHALL BE HAULED OFF SITE DUE TO NO ONSITE STORAGE LOCATIONS.
 **ALL FILL MATERIAL (EMBANKMENT) SHALL BE BROUGHT IN FROM OFF-SITE LOCATION, SINCE THE ONSITE EXCAVATED MATERIAL MUST BE HAULED OFF SITE.

CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID		
STATION	OFFSET (FEET)	QUANTITY (EACH)
EAST AVENUE 20+97	9.5' RT	1
TOTAL QUANTITY =		1

VALVE VAULTS TO BE ADJUSTED		
STATION	OFFSET (FEET)	QUANTITY (EACH)
PINE AVENUE 3+88	18' LT	1
TOTAL QUANTITY =		1

HANDHOLE		
STATION	OFFSET (FEET)	QUANTITY (EACH)
EAST AVENUE 21+84	17' RT	1
TOTAL QUANTITY =		1

MANHOLES TO BE ADJUSTED		
STATION	OFFSET (FEET)	QUANTITY (EACH)
EAST AVENUE 21+03	13' LT	1
TOTAL QUANTITY =		1

VALVE VAULTS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID		
STATION	OFFSET (FEET)	QUANTITY (EACH)
EAST AVENUE 21+95	10' LT	1
22+07	17' RT	1
22+15	17' RT	1
TOTAL QUANTITY =		3

HANDHOLE TO BE ADJUSTED		
STATION	OFFSET (FEET)	QUANTITY (EACH)
PINE AVENUE 3+17	21' LT	1
TOTAL QUANTITY =		1

MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID		
STATION	OFFSET (FEET)	QUANTITY (EACH)
PINE AVENUE 1+80	2' LT	1
2+42	1' RT	1
2+81	18' RT	1
4+11	8' RT	1
4+70	6' RT	1
4+97	10' LT	1
EAST AVENUE 22+06	88' RT	1
23+12	9' LT	1
TOTAL QUANTITY =		8

VALVE BOXES TO BE ADJUSTED		
STATION	OFFSET (FEET)	QUANTITY (EACH)
PINE AVENUE 4+04	30' L	1
TOTAL QUANTITY =		1

REMOVE EXISTING HANDHOLE		
STATION	OFFSET (FEET)	QUANTITY (EACH)
EAST AVENUE 21+84	17' RT	1
TOTAL QUANTITY =		1

HANDHOLE TO BE ADJUSTED WITH NEW FRAME AND COVER		
STATION	OFFSET (FEET)	QUANTITY (EACH)
PINE AVENUE 3+96	39' LT	1
TOTAL QUANTITY =		1

MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID		
STATION	OFFSET (FEET)	QUANTITY (EACH)
PINE AVENUE 4+92	16' RT	1
TOTAL QUANTITY =		1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAU ROUTES 1472 & 3569
 VILLAGE OF RIVERSIDE
 RAILWAY/WATER TOWER CAMPUS RESTORATION PROJECT

SCHEDULE OF QUANTITIES

SCALE: N/A
 DATE: 12/01/08

DRAWN BY SMP
 CHECKED BY BDH