

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	CONST. CODE 1000 QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,210
40600300	AGGREGATE (PRIME COAT)	TON	27
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	850
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	252
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,360
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	11,948
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	14
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	22
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	72
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	162
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	10,332
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	256
67100100	MOBILIZATION	L SUM	1
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	146
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	49
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	20,495
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	15
* XX006425	RESTORATION	SQ YD	73
△ Z007660	TRAINEES	HOURL	500
XX007167	HOT-MIX ASPHALT DRIVEWAY, 1 3/4"	SQ YD	412

* INDICATES SPECIALTY ITEMS
 △ Y080

Pictured: March 31, 2009 @ 9:11 AM By: Kris Plung - Tab: 03_Sum of Quant 22534
 Path: H:\S\KSR004\CH0803\DWG\DWG_FINAL_ENG\CH0803-CVR

COPYRIGHT © 2009 ENGINEERING ENTERPRISES, INC.



Engineering Enterprises, Inc.
 CONSULTING ENGINEERS
 52 Wheeler Road
 Sugar Grove, Illinois 60554
 630.466.6700 / www.eeiweb.com

VILLAGE OF CAMPTON HILLS
 KANE COUNTY, ILLINOIS

1	02-17-09	REVISED PER IDOT COMMENTS
NO.	DATE	REVISIONS

McDONALD ROAD
LAPP IMPROVEMENTS

SUMMARY OF QUANTITIES

DATE: DECEMBER 2008
 PROJECT NO: CH0803
 FILE: CH0803-CVR
 SHEET **3** OF **12**