

F. A. U. RITE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0281	07-00050-00-FP	WILL	33	2
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT #63157

S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	PAVEMENT	
					CONST. TYPE CODE	
					1000	
	20200100	EARTH EXCAVATION	CU YD	5179	5179	
	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	100	100	
	20800150	TRENCH BACKFILL	CU YD	1798	1798	
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	5299	5299	
	21300010	EXPLORATION TRENCH, SPECIAL	FOOT	80	80	
	25200650	SODDING, SALT TOLERANT (SPECIAL)	SQ YD	5299	5299	
	28000400	PERIMETER EROSION BARRIER	FOOT	4115	4115	
	28000510	INLET FILTERS	EACH	23	23	
	35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	1468	1468	
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	100	100	
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3296	3296	
	40600300	AGGREGATE (PRIME COAT)	TON	24	24	
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	75	75	
	40701811	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 6 1/2"	SQ YD	2014	2014	
	40701881	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	SQ YD	9422	9422	
	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	348	348	
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	13215	13215	
	42400800	DETECTABLE WARNINGS	SQ FT	272	272	
	44000100	PAVEMENT REMOVAL	SQ YD	10258	10258	
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	663	663	
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	238	238	
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	4356	4356	
	44000600	SIDEWALK REMOVAL	SQ FT	12420	12420	
	55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	490	490	
	55019600	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 15"	FOOT	40	40	
	55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	55	55	
	55021700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 15"	FOOT	738	738	
	55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18"	FOOT	170	170	
	55022200	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30"	FOOT	278	278	
	55022400	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 36"	FOOT	246	246	
	55022500	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 42"	FOOT	130	130	
	55100400	STORM SEWER REMOVAL 10"	FOOT	86	86	
	55100500	STORM SEWER REMOVAL 12"	FOOT	333	333	
	55100700	STORM SEWER REMOVAL 15"	FOOT	247	247	
	55101600	STORM SEWER REMOVAL 36"	FOOT	459	459	
	55101800	STORM SEWER REMOVAL 42"	FOOT	220	220	
*	56106300	ADJUSTING WATER MAIN 6"	FOOT	30	30	
*	56106400	ADJUSTING WATER MAIN 8"	FOOT	30	30	
*	56106600	ADJUSTING WATER MAIN 12"	FOOT	30	30	
*	56400100	FIRE HYDRANTS TO BE MOVED	EACH	3	3	
	59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	31	31	
	60107600	PIPE UNDERDRAINS 4"	FOOT	300	300	
	60201105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	5	5	
	60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	2	2	
	60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1	1	
	60207905	CATCH BASINS, TYPE C, TYPE 11 FRAME AND GRATE	EACH	1	1	
	60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	2	2	
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6	6	
	60219300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	4	4	

\* - INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE
IDOT REVIEW	2-24-2009

ILLINOIS DEPARTMENT OF TRANSPORTATION

**NORMANTOWN ROAD RECONSTRUCTION  
ROMEOWILLE  
SUMMARY OF QUANTITIES**

SCALE: VERT. N/A  
HORIZ. N/A  
DATE 01/19/2009

DRAWN BY JJB/JRA  
CHECKED BY BDB