

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE I000	
				MCHENRY COUNTY	LAKE COUNTY
20201006	GRADING AND SHAPING SHOULDERS	UNIT	10	8	2
35101600	AGGREGATE BASE COURSE, TYPE B 4 INCH	SQ YD	5	5	0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	1,322	1,136	186
40600300	AGGREGATE (PRIME COAT)	TON	27	23	4
40600625	LEVELING BINDER (MACHINE METHOD) N50	TON	560	453	107
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	0
40600982	HOT MIX ASPHALT SURFACE REMOVAL, BUTT JOINT	SQ YD	883	799	84
40603335	HOT MIX ASPHALT SURFACE COURSE, MIX "C" , N50	TON	940	780	160
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	40	40	0
42400800	DETECTABLE WARNINGS	SQ FT	12	12	0
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	12,322	10,555	1,767
44000600	SIDEWALK REMOVAL	SQ FT	40	40	0
44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	266	228	38
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	530	455	75
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	925	795	130
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	925	795	130
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	13,207	11,355	1,852
48101200	AGGREGATE SHOULDERS, TYPE B	TON	436	373	63
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	14	12	2
67100100	MOBILIZATION	LSUM	1	1	0
70101700	TRAFFIC CONTROL AND PROTECTION	LSUM	1	1	0
70300100	SHORT TERM PAVEMENT MARKING	FOOT	4,750	4069	681
7030100	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,584	1,357	227
78000200	THERMOPLASTIC PAVEMENT MARKING LINE, 4"	FOOT	19,000	16,276	2,724
78000650	THERMOPLASTIC PAVEMENT MARKING LINE, 24"	FOOT	66	39	27
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	270	231	39

* INDICATES SPECIALTY ITEM

SCHEDULE OF QUANTITIES

THERMOPLASTIC PAVEMENT MARKING LINE, 24"	
STA	LENGTH (FT)
0+18	25.0
13+35	14.0
47+36	27.0
TOTAL	66.0 FT

PCC SIDEWALK, 5"	
LOCATION	AREA (SQ FT)
0+26	20.0
13+00	20.0
TOTAL	40.0 SQ FT

FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	
STATION	QTY
0+24	1.0
13+45	1.0
13+57	1.0
16+40	1.0
16+80	1.0
17+20	1.0
17+62	1.0
18+03	1.0
27+91	1.0
36+13	1.0
36+14	1.0
37+52	1.0
43+06	1.0
46+97	1.0
TOTAL	14.0

DETECTABLE WARNINGS	
LOCATION	AREA (SQ FT)
0+26	6.0
13+00	6.0
TOTAL	12.0 SQ FT

SIDEWALK REMOVAL	
LOCATION	AREA (SQ FT)
0+26	20.0
13+00	20.0
TOTAL	40.0 SQ FT

HMA SURFACE REMOVAL, BUTT JOINT				
LOCATION	LENGTH	WIDTH	AREA (SQ YD)	
0+08	115.0	4.5	57.5	
13+38	28.0	4.5	14.0	
25+02	59.0	4.5	29.5	
27+96	38.5	4.5	19.3	
30+75	32.5	4.5	16.3	
33+34	48.3	4.5	24.2	
36+09	32.0	4.5	16.0	
39+03	60.0	4.5	30.0	
47+57	124.0	4.5	62.0	
DRIVEWAYS				
1+24			3.9	
2+01			12.0	
2+15			8.1	
2+80			11.4	
3+39			13.6	
4+07			13.8	
4+85			10.2	
5+98			18.2	
6+79			11.4	
7+91			14.4	
8+73			8.6	
9+41			11.7	
10+34			14.3	
10+73			13.0	
11+38			9.2	
12+36			9.1	
14+50			13.6	
16+62			19.3	
17+50			76.6	
19+65			7.1	
20+53			22.7	
21+43			26.0	
23+16			12.2	
24+12			5.6	
25+21			18.4	
25+82			13.6	
26+12			5.0	
26+82			18.2	
27+36			25.7	
27+60			9.8	
29+01			6.9	
29+35			32.2	
29+39			7.0	
31+00			11.0	
31+56			11.7	
32+36			7.7	
32+62			7.2	
34+66			11.0	
36+00			22.4	
37+87			12.1	
38+25			6.2	
41+88			5.8	
45+65			2.0	
45+84			14.3	
TOTAL			883.0	

COPYRIGHT © 2008 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 566 PAGES
 3/14/2009
 C:\WORK\080895\p080895.dwg
 P:\WORK\080895\p080895.dwg
 P:\WORK\080895\p080895.dwg
 P:\WORK\080895\p080895.dwg
 P:\WORK\080895\p080895.dwg
 P:\WORK\080895\p080895.dwg



USER NAME = 566bod	DESIGNED - JGH	REVISED -
FILE NAME = 080851-S00.whd	DRAWN - BCD	REVISED -
PLOT DATE = 3/2/2009	CHECKED - TAO	REVISED -
	DATE - 3-13-09	REVISED -

**VILLAGE OF LAKEMOOR, ILLINOIS
 FAU 0012 WEST WEGNER ROAD/SOUTH DRIVE
 STP (LAPP)IMPROVEMENTS**

**SUMMARY OF QUANTITIES AND
 SCHEDULE OF QUANTITIES**

SCALE: NONE

STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	08-00008-00-RS	MCHENRY	15	3
FED. ROAD DIST. NO.		CONTRACT NO. 63165		
C-91-204-09		ILLINOIS FED. AID PROJECT M-9003(Q70)		

*F.A.U. 0012 WEST WEGNER ROAD/SOUTH DRIVE