


**SUMMARY OF QUANTITIES**

*SFTY-1B*

CODE NUMBER	PAY ITEM DESCRIPTION	UNITS	TOTALS
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNITS	60
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNITS	96
20101100	TREE TRUNK PROTECTION	EACH	10
20101200	TREE ROOT PRUNING	EACH	10
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	854
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2,918
25000210	SEEDING, CLASS 2A	ACRE	0.60
42001300	PROTECTIVE COAT	SQ YD	4,850
42400430	PORTLAND CEMENT CONCRETE SIDEWALK, 5-INCH, SPECIAL	SQ FT	42,966
42400800	DETECTABLE WARNINGS	SQ FT	408
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	680
44000600	SIDEWALK REMOVAL	SQ FT	17,627
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	449
* 56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	3
* 56400800	FIRE HYDRANT AND VALVE TO BE MOVED	EACH	5
60266600	VALVE BOXES TO BE ADJUSTED	EACH	8
67100100	MOBILIZATION	L SUM	1
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
Z0017400	DRAINAGE AND UTILITY STRUCTURES TO BE ADJUSTED	EACH	22
Z0022800	FENCE REMOVAL	FOOT	120
XX006806	HOT-MIX ASPHALT DRIVEWAY PAVEMENT	SQ YD	365

\* SAFETY ITEMS

 <b>SEC Group, Inc.</b> <small>Professional Design Firm # 184-000108</small> Engineering Surveying Planning Landscape Architecture Illinois • Texas • Georgia www.secgroup.com	USER NAME = jstrzelko	DESIGNER = JJS	REVISED -	<b>VILLAGE OF MUNDELEIN</b>	<b>SUMMARY OF QUANTITIES</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1:20	DRAWN = JJS	REVISED -						08-00086-00-SW	LAKE	40	3	
	PLOT DATE = 4/1/2009	CHECKED = JLP	REVISED -						CONTRACT NO. 63166		FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	
				SCALE: 1:20    SHEET NO. 1 OF 1 SHEETS    STA. NA    TO STA. NA									