

## SUMMARY OF QUANTITIES

CODE	PAY ITEM	UNIT	1000	1000
			TOTAL QUANTITY	80% FEDERAL 20% LOCAL
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQYD	500	500
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	10	10
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	10	10
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	10	10
25200100	SODDING	SQYD	500	500
25200200	SUPPLEMENTAL WATERING	UNIT	20	20
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	60	60
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	2,500	2,500
40600300	AGGREGATE (PRIME COAT)	TON	60	60
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQYD	225	225
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX D, N50	TON	1,350	1,350
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	20	20
42101300	PROTECTIVE COAT	SQYD	600	600
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQYD	250	250
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQFT	1,100	1,100
~ 42400800	DETECTABLE WARNINGS	SQFT	128	128
~ 44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQYD	11,850	11,850
~ 44000200	DRIVEWAY PAVEMENT REMOVAL	SQYD	450	450
~ 44000600	SIDEWALK REMOVAL	SQFT	1,350	1,350
~ 44001700	COMBINATION CONC CURB AND GUTTER REMOVAL AND REPL	FOOT	1,000	1,000
~ 44201325	CLASS C PATCHES, TYPE I, 8 INCH	SQYD	45	45
~ 44201329	CLASS C PATCHES, TYPE II, 8 INCH	SQYD	135	135
~ 44201333	CLASS C PATCHES, TYPE III, 8 INCH	SQYD	45	45
~ 44201335	CLASS C PATCHES, TYPE IV, 8 INCH	SQYD	175	175
~ 60228110	MANHOLES, SANITARY, 4' DIA., TY 1 FRAME, CLOSED LID	EACH	2	2
~ 60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	3	3
~ 60257900	MANHOLES TO BE RECONSTRUCTED	EACH	20	20
~ 60266610	VALVE BOXES TO BE ADJUSTED (SPECIAL)	EACH	3	3
~ 60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	3	3
~ 60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	32	32
~ 60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	3	3
~ 60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	32	32
~ 60500105	FILLING MANHOLES	EACH	1	1
67100100	MOBILIZATION	L SUM	1	1
~ 70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1
~ 70106800	CHANGEABLE MESSAGE SIGN	CAL-MO	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	750	750
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQFT	100	100
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5,000	5,000
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	450	450
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	475	475
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	175	175
~ X0517100	STORM SEWERS, DUCTILE IRON PIPE 8"	FOOT	12	12
~ X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	575	575
~ XX104100	CONNECTION TO EXISTING MANHOLE	EACH	3	3
~ Z0004900	BITUMINOUS MIXTURE FOR PATCHING POTHOLES (HOT MIX)	TON	20	20
~ <b>Δ</b> Z0076600	TRAINEES	hour	500	500

**Δ Y070**  
 \* DENOTES SPECIALTY ITEM  
 ~ DENOTES THAT A SPECIAL PROVISION HAS BEEN PROVIDED

Drawing file: W:\Projects\5650236 - 8th Avenue LAPP\SUMM01.dwg Mar 18, 2009 - 9:08am

**HANCOCK ENGINEERING**  
 Civil Engineers  
 Municipal Consultants  
 Established 1911

USER NAME	DESIGNED	WOP	REVISED
	DRAWN	MK/LEV	
PLOT SCALE	CHECKED	JCG	
PLOT DATE	DATE	3-16-09	

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: NONE SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2733	08-00128-00-RS	COOK	14	4
CONTRACT NO. 63172			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	