

## INDEX OF SHEETS



























SHEET NO.	DESCRIPTION
1	COVER SHEET, LOCATION MAP
2	INDEX OF SHEETS, LEGEND OF SYMBOLS, AND I.D.O.T. STANDARD DRAWINGS
3	GENERAL NOTES
4	SUMMARY OF QUANTITIES
5-6	EXISTING TYPICAL CROSS SECTIONS AND PROPOSED TYPICAL CROSS SECTIONS
7	DETAILS & NOTES
8-11	PAVING PLANS
12	TRAFFIC SIGNAL DETECTOR LOOP REPLACEMENT PLAN
13	DETAILS FOR FRAMES AND LIDS ADJUSTMENT WITH MILLING (BD 08)
14	CURB AND GUTTER REMOVAL AND REPLACEMENT (BD 24)
15	BUTT JOINT AND HMA TAPER DETAILS (BD 32)
16	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS (TC 10)
17	DISTRICT ONE TYPICAL PAVEMENT MARKINGS (TC 13)
18	TRAFFIC CONTROL AND PROTECTIONS AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC) (TC 14)
19	DISTRICT ONE - DETECTOR LOOP INSTALLATION DETAILS FOR ROADWAY RESURFACING (TS 07)

## I.D.O.T. STANDARD DRAWINGS


STANDARD NO.	TITLE OR DESCRIPTION
000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
424001-05	CURB RAMPS FOR SIDEWALKS
442201-03	CLASS C&D PATCHES
604001-03	FRAMES AND LIDS, TYPE 1
701501-05	URBAN LANE CLOSURE, 2-LANE, 2-WAY, UNDIVIDED
701606-06	URBAN LANE CLOSURE, MULTILANE, 2-WAY, WITH MOUNTABLE MEDIAN
701701-06	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701801-04	LANE CLOSURE, MULTILANE, 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
701901-01	TRAFFIC CONTROL DEVICES
780001-02	TYPICAL PAVEMENT MARKINGS

## LEGEND OF SYMBOLS

(TO BE USED IN CONJUNCTION WITH I.D.O.T. STANDARD 000001-05)

SYMBOL	DESCRIPTION
	EXISTING HOT-MIX ASPHALT AREA
	EXISTING CONCRETE AREA
	EXISTING GRASS AREA
	PROPOSED HOT-MIX ASPHALT BUTT JOINT
	EXISTING CONCRETE SIDEWALK OR DRIVEWAY REMOVAL
	PROPOSED CONCRETE AREA, 5" SIDEWALK, 7" DRIVEWAY
	PROPOSED HOT-MIX ASPHALT PAVING AREA
	PROPOSED CLASS D PATCHES
	PROPOSED DETECTABLE WARNINGS
<b>A</b>	STRUCTURE TO BE ADJUSTED
<b>A*</b>	STRUCTURE TO BE ADJUSTED (SPECIAL)
<b>1C</b>	NEW FRAME AND LID, TYPE 1, CLOSED LID
<b>1P</b>	NEW FRAME AND LID, TYPE 1, OPEN LID
<b>RC</b>	STRUCTURE TO BE RECONSTRUCTED
	EXISTING DOMESTIC WATER SERVICE BOX
	EXISTING FIRE HYDRANT
	EXISTING WATER VALVE BOX
	EXISTING WATER MAIN VALVE VAULT
	EXISTING STORM SEWER INLET
	EXISTING STORM SEWER CATCH BASIN
	EXISTING SEWER MANHOLE
	EXISTING STREET LIGHT POLE
	EXISTING POWER POLE
	EXISTING TRAFFIC SIGNAL POLE
	EXISTING TRAFFIC SIGNAL MAST ARM
	EXISTING HANDHOLE
	DOUBLE HANDHOLE
	EXISTING TRAFFIC SIGNAL OR STREET LIGHT CONTROLLER
	EXISTING TRAFFIC SIGNAL MANHOLE
	EXISTING CURB AND GUTTER
	PROPOSED COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT

Drawing file: W:\Projects\00008233 - 9th Avenue LAPP\INDEX.dwg Mar 20, 2009 - 4:34pm

 <p><b>HANCOCK ENGINEERING</b> Civil Engineers Municipal Consultants Established 1911</p>	USER NAME	DESIGNED <b>WOP</b>	REVISED	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>INDEX OF SHEETS, I.D.O.T. STANDARD DRAWINGS, AND LEGEND OF SYMBOLS</b>	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE	DRAWN <b>LEV/MK</b>	REVISED			2733	08-00112-00-RS	COOK	19	2
	PLOT DATE	CHECKED <b>JCG</b>	REVISED			CONTRACT NO. 63173				
						SCALE: NONE    SHEET NO. OF SHEETS STA. TO STA.    FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
						E.H.E. PROJECT NO. 600-08-23301				