

SUMMARY OF QUANTITIES

CODE	PAY ITEM	UNIT	1000 TOTAL QUANTITY	1000 MELROSE PARK 80%FEDERAL 20%LOCAL	1000 MAYWOOD 80%FEDERAL 20%LOCAL
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQYD	300	250	50
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	10	8	2
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	10	8	2
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	10	8	2
25200100	SODDING	SQYD	300	250	50
25200200	SUPPLEMENTAL WATERING	UNIT	10	8	2
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	100	83	17
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	4,600	3,820	780
40600300	AGGREGATE (PRIME COAT)	TON	100	83	17
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	17	3
40600895	CONSTRUCTING TEST STRIP	EACH	1	0.83	0.17
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQYD	300	250	50
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX D, N50	TON	2,500	2,075	425
~ 40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	50	40	10
42101300	PROTECTIVE COAT	SQYD	500	415	85
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQYD	250	210	40
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQFT	1,000	830	170
~ 42400800	DETECTABLE WARNINGS	SQFT	128	24	104
~ 44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQYD	22,500	18,675	3,825
~ 44000200	DRIVEWAY PAVEMENT REMOVAL	SQYD	500	400	100
~ 44000600	SIDEWALK REMOVAL	SQFT	1,100	900	200
~ 44001700	COMB CONC CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	650	590	60
~ 44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQYD	75	65	10
~ 44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQYD	150	125	25
~ 60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2	0
~ 60266610	VALVE BOXES TO BE ADJUSTED (SPECIAL)	EACH	1	1	0
~ 60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	8	6	2
~ 60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	62	47	15
~ 60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	8	6	2
~ 60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	62	47	15
~ 67100100	MOBILIZATION	L SUM	1	0.83	0.17
~ 70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	0.83	0.17
~ 70106800	CHANGEABLE MESSAGE SIGN	CAL-MO	1	0.83	0.17
~ 70300100	SHORT TERM PAVEMENT MARKING	FOOT	3,500	2,905	595
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQFT	160	130	30
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11,100	9,220	1,880
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,500	1,250	250
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	550	460	90
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	400	335	65
* ~ 88600600	DETECTOR LOOP REPLACEMENT	FOOT	125	125	0
~ X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,100	910	190
~ Z0004900	BITUMINOUS MIXTURE FOR PATCHING POTHOLES (HOT MIX)	TON	20	17	3
~ Δ Z0076600	TRAINEES	HOUR	500	415	85

Δ **Y080**
 * DENOTES SPECIALTY ITEM
 ~ DENOTES THAT A SPECIAL PROVISION HAS BEEN PROVIDED

Drawing file: W:\Projects\60008233 - 9th Avenue LAPP\Summary.dwg Mar 20, 2009 - 4:36pm



USER NAME	DESIGNED	WOP	REVISED
	DRAWN	LEV/MK	REVISED
PLOT SCALE	CHECKED	JCG	REVISED
PLOT DATE	DATE	3-23-09	REVISED

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2733	08-00112-00-RS	COOK	19	4
SCALE:			SHEET NO. OF SHEETS	STA. TO STA.
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 63173	