

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY X028-2A	
				80% FED	20% STATE
20100500	TREE REMOVAL, ACRES	ACRE	0.19	0.19	
20200100	EARTH EXCAVATION	CU YD	535	535	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS	CU YD	455	45.5	
20300100	CHANNEL EXCAVATION	CU YD	109	109	
25100630	EROSION CONTROL BLANKET	SQ YD	388	388	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	54	54	
28000300	TEMPORARY DITCH CHECKS	EACH	1	1	
28000400	PERIMETER EROSION BARRIER	FOOT	142	142	
28000500	INLET AND PIPE PROTECTION	EACH	4	4	
28100107	STONE RIPRAP, CLASS A4	SQ YD	225	225	
28200200	FILTER FABRIC	SQ YD	225	225	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	260	260	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	22	22	
40600990	TEMPORARY RAMP	SQ YD	56	56	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	104	104	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	10	10	
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	47	47	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	47	47	
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	399	399	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	57	57	
48203019	HOT-MIX ASPHALT SHOULDERS, 5 1/2"	SQ YD	174	174	
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	550	550	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1	
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	113	113	
50800105	REINFORCEMENT BARS	POUND	47260	47260	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	630	630	
50800615	BAR SPLICERS	EACH	88	88	
51500100	NAME PLATES	EACH	1	1	
54003000	CONCRETE BOX CULVERTS	CU YD	215.2	215.2	

* SPECIALTY ITEMS

FILE NAME =	USER NAME = hensonke	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cs\pw_work\PWIDOT\HENSONKE\dms34329\d18010rv.dgn		DRAWN -	REVISED -			599	103MFT-T	ROCK ISLAND	55	3	
		CHECKED -	REVISED -			CONTRACT NO. 64737					
		DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.