

SCHEDULE OF QUANTITIES

70301000 WORKZONE PAVEMENT MARKING REMOVAL

SO_FT	LOCATION	REMARKS
Stage 2		
148	RT. STA. 992 + 57 TO	997 + 0 Stage 2 outside edge line
107	RT. STA. 997 + 0 TO	999 + 83 Stage 2 outside edge line
148	RT. STA. 992 + 57 TO	997 + 0 Stage 2 inside edge line
107	RT. STA. 997 + 0 TO	999 + 83 Stage 2 inside edge line
Stage 3		
148	RT. STA. 992 + 57 TO	997 + 0 Stage 3 outside edge line
107	RT. STA. 997 + 0 TO	999 + 83 Stage 3 outside edge line
148	RT. STA. 992 + 57 TO	997 + 0 Stage 3 inside edge line
107	RT. STA. 997 + 0 TO	999 + 83 Stage 3 inside edge line
20	RT. STA. 992 + 57	Stop Bar
20	LT. STA. 1000 + 21	Stop Bar
Short term		
12	CL STA. 995 + 64 TO	997 + 2 Short term pavement
1070	TOTAL	

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION	REMARKS
Stage 2		
62.5	RT/LT 994 + 77 TO	995 + 39 Taper - Stage 2
112.5	RT 995 + 10 TO	996 + 22 Outside edge barrier wall - Stage 2
187.5	LT 995 + 39 TO	997 + 27 Tangent Section - Stage 2
75	LT/RT 997 + 27 TO	997 + 89 Taper - Stage 2
75	RT 994 + 2 TO	994 + 77 Taper - Stage 3
75	RT 997 + 89 TO	998 + 64 Taper - Stage 3
587.5	TOTAL	

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION	REMARKS
stage 3		
62.5	LT 994 + 77 TO	995 + 39 Taper Section - Stage 3
187.5	LT 995 + 39 TO	997 + 27 Tangent Section - Stage 3
62.5	LT/RT 997 + 27 TO	997 + 89 Taper - Stage 3
312.5	TOTAL	

78001110 PAINT PAVEMENT MARKING LINE - 4"

FOOT	LOCATION	REMARKS
763	LT 992 + 57 TO	1000 + 21 Edge line
763	RT 992 + 57 TO	1000 + 21 Edge line
191	CL 992 + 57 TO	1000 + 21 Skip dashes
1717	TOTAL	

78100100 RAISED REFLECTIVE PAVEMENT MARKERS

EACH	LOCATION	REMARKS
11	CL 992 + 57 TO	1000 + 21
11	TOTAL	

78200410 GUARDRAIL MARKERS, TYPE A

EACH	LOCATION	REMARKS
4	RT. STA. 996 + 31 TO	997 + 93 Minimum of 4 required
4	TOTAL	

78201000 TERMINAL MARKERS (DIRECT APPLIED)

EACH	LOCATION	REMARKS
1	RT. STA. 995 + 81	End of Type 1 (Special) Tangent
1	RT. STA. 998 + 43	End of Type 1 (Special) Tangent
2	TOTAL	

78300105 PAVEMENT MARKING REMOVAL

FOOT	LOCATION	REMARKS
Stage 2		
243	CL 992 + 57 TO	995 + 0 Skips - Stage 2
445	LT 994 + 10 TO	998 + 55 Edge line - Stage 2
271	CL 997 + 50 TO	1000 + 21 Skips - Stage 2
Stage 3		
505	LT 993 + 80 TO	998 + 85 Edge line - Stage 3
1464	TOTAL	

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

EACH	LOCATION	REMARKS
11	CL 992 + 57 TO	1000 + 21
11	TOTAL	

A2006514 TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1 3/4" CALIPER, BALLED AND BURLAPPED

EACH	LOCATION	REMARKS
64	LOCATION TO BE DETERMINED BY LANDSCAPE ARCHITECT	
64	TOTAL	

C2001748 SHRUB, CORNUS SERICEA CARDINAL (CARDINAL REDOSIER DOGWOOD), 4' HEIGHT, BALLED AND BURLAPPED

EACH	LOCATION	REMARKS
24	LOCATION TO BE DETERMINED BY LANDSCAPE ARCHITECT	
24	TOTAL	

X0323988 TEMPORARY SOIL RETENSION SYSTEM

SO_FT	LOCATION	REMARKS
485	RT 996 + 34	Double 7' x 7' Box Culvert
485	TOTAL	

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION	REMARKS
1	LT. STA. 996 + 77	Stage 2 - Narrow Setup
1	LT. STA. 997 + 89	Stage 2
1	LT. STA. 996 + 10	Stage 2 - Narrow Setup
1	LT. STA. 996 + 22	Stage 2 - Narrow Setup
4	TOTAL	

Z0030335 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION	REMARKS
1	RT. STA. 994 + 2	Stage 3 - Narrow Setup
1	RT. STA. 998 + 68	Stage 3
2	TOTAL	