

# EARTHWORK SCHEDULE

			20200100	EARTH			EARTHWORK	250001000	25000210	25000310	28000250	20201200		
LOCATION			EARTH	EXCAVATION	EMBANKMENT	BALANCE	SEEDING	SEEDING	SEEDING	TEMPORARY	REMOVAL			
			EXCAVATION	ADJUSTED FOR SHRINKAGE	(FILL)	WASTE (+)	CLASS 1	CLASS 2A	CLASS 4	EROSION CONTROL	AND DISPOSAL OF UNSUITABLE MATERIAL			
			(CU YD)	(CU YD)	(CU YD)	(CU YD)	(ACRE)	(ACRE)	(ACRE)	(POUND)	(CU YD)			
			<b>Mainline (IL 92)</b>	993 + 50	TO 999 + 50	425.6	319.2	254.2	65.0	0.06	0.11	0.02	54.0	45.5
			<b>Streambed</b>	10 + 00	TO 11 + 00	108.8	81.6	48.7	32.9					
			<b>TOTALS</b>			534.4	400.8	302.9	97.9	0.06	0.11	0.02	54.0	45.5