

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	STEPHENSON COUNTY	WINNEBAGO COUNTY	STEPHENSON COUNTY	STEPHENSON COUNTY	STEPHENSON COUNTY	WINNEBAGO COUNTY	WINNEBAGO COUNTY	WINNEBAGO COUNTY	WINNEBAGO COUNTY	WINNEBAGO COUNTY
				FHWA 80% STATE 20% 1000-2A	FHWA 80% STATE 20% 1000-2A	FHWA 80% STATE 20% X081-2A SN 089-0084 (BRIDGE OVER ROCK RUN)	FHWA 80% STATE 20% Y007-2A	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% Y007-2A	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% X028-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	788	37	751								
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	848	42	806								
20100500	TREE REMOVAL, ACRES	ACRE	1.00	0.80	0.20								
20101000	TEMPORARY FENCE	FOOT	2,270	670	1,600								
20200100	EARTH EXCAVATION	CU YD	76,013	12,119	63,894								
20200200	ROCK EXCAVATION	CU YD	6,479		6,479								
20200410	EARTH EXCAVATION (SPECIAL)	CU YD	10	5	5								
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2,208				529	164	310	176	162	369	498
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	125			125							
20800150	TRENCH BACKFILL	CU YD	114		114								
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1,065		1,065								
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	11,735	3,518	8,217								
21101600	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	SQ YD	18,700	9,799	8,901								
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	29,129	10,179	18,950								
* 25000100	SEEDING, CLASS 1	ACRE	1.00		1.00								
* 25000210	SEEDING, CLASS 2A	ACRE	16.50	6.25	10.25								
* 25000310	SEEDING, CLASS 4	ACRE	4.00	1.00	3.00								
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,930	657	1,273								
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1,930	657	1,273								
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,930	657	1,273								
* 25000750	MOWING	ACRE	17.50	6.25	11.25								
* 25100115	MULCH, METHOD 2	ACRE	13.00	3.75	9.25								
* 25100630	EROSION CONTROL BLANKET	SQ YD	35,298	15,876	19,422								
* 25100900	TURF REINFORCEMENT MAT	SQ YD	5,629	1,018	4,611								
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	17,153	5,838	11,315								
28000300	TEMPORARY DITCH CHECKS	EACH	373	154	219								
28000400	PERIMETER EROSION BARRIER	FOOT	11,584	3,148	8,436								
28000500	INLET AND PIPE PROTECTION	EACH	48	14	34								
28100107	STONE RIPRAP, CLASS A4	SQ YD	1,880			1,027	212	138	170	100	46	103	84

DENOTES SPECIALTY ITEMS

● NON-PARTICIPATING 100% STATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 505 (IL 75)

SUMMARY OF QUANTITIES

SCALE: VERT. _____
HORIZ. _____
DATE: 3/3/09

DRAWN BY MTH
CHECKED BY SPF

PLOT DATE = 3/4/2009
 FILE NAME = K:\119568\11_75_3P_EastCAD\Design\195681_500.dgn
 USER NAME = JTR
 MODEL = S00-1