

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
505	111RS-4, 111BR-1, Yc-15d-RS-1, & (W-15d)T-1	STEPHENSON & WINNEBAGO	335	6
STA.		TO STA.		
FED. ROAD DIST. NO. 2		ILLINOIS		FED. AID PROJECT
CONTRACT NO. 64970				

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	STEPHENSON COUNTY	WINNEBAGO COUNTY	STEPHENSON COUNTY	STEPHENSON COUNTY	STEPHENSON COUNTY	WINNEBAGO COUNTY	WINNEBAGO COUNTY	WINNEBAGO COUNTY	WINNEBAGO COUNTY	WINNEBAGO COUNTY
				FHWA 80% STATE 20% 1000-2A	FHWA 80% STATE 20% 1000-2A	FHWA 80% STATE 20% X081-2A	FHWA 80% STATE 20% Y007-2A	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% Y007-2A	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% X028-2A
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	1,266	1,266									
28200200	FILTER FABRIC	SQ YD	3,146	1,266		1,027	212	138	170	100	46	103	84
28300470	AGGREGATE DITCH 12"	SQ YD	3,301	1,457	1,844								
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	23,528	1,797	21,731								
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	5,678	275	5,403								
35300405	PORTLAND CEMENT CONCRETE BASE COURSE 9 1/4"	SQ YD	1,396	997	399								
35300510	PORTLAND CEMENT CONCRETE BASE COURSE 10 1/2"	SQ YD	361		361								
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	205	103	102								
40600300	AGGREGATE (PRIME COAT)	TON	1,307	704	603								
40600525	LEVELING BINDER (HAND METHOD), N50	TON	10	5	5								
40600627	LEVELING BINDER (MACHINE METHOD), 1L-9.5FG, N50	TON	21,357	13,290	8,067								
40600895	CONSTRUCTING TEST STRIP	EACH	2	1	1								
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	4,723	2,992	1,731								
40600990	TEMPORARY RAMP	SQ YD	1,008	496	512								
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	638	381	257								
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,060	243	817								
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	32,240	14,543	17,697								
40701921	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 12"	SQ YD	23,454	663	22,791								
40702700	FURNISH PROFILOGRAPH	L SUM	1		1								
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	2,587	1,470	1,117								
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	249	249									
42001200	PAVEMENT FABRIC	SQ YD	1,757	997	760								
42001300	PROTECTIVE COAT	SQ YD	2,003	450	983	570							
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	35	35									
44000100	PAVEMENT REMOVAL	SQ YD	15,401	1,158	14,243								
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	114,226	63,649	50,577								
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	8,610		8,610								
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	3,905		3,905								
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1,747		1,747								

• DENOTES SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 505 (IL 75)

SUMMARY OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE: 3/3/09

DRAWN BY MTH
CHECKED BY SPF

PLOT DATE = 3/3/2009
FILE NAME = K:\11195800\11_75_3P_East\CADD\Design\195801_500.dgn
USER = J...
MODEL = S00-2