

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
505	111RS-4, 111BR-1, Yo-15d-RS-1, & (W-15d)T-1	STEPHENSON & WINNEBAGO	335	8
STA.		TO STA.		
FED. ROAD DIST. NO. 2		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 64970				

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	STEPHENSON COUNTY	WINNEBAGO COUNTY	STEPHENSON COUNTY	STEPHENSON COUNTY	STEPHENSON COUNTY	WINNEBAGO COUNTY	WINNEBAGO COUNTY	WINNEBAGO COUNTY	WINNEBAGO COUNTY	WINNEBAGO COUNTY
				FHWA 80% STATE 20% 1000-2A	FHWA 80% STATE 20% 1000-2A	FHWA 80% STATE 20% X081-2A SN 089-0084 (BRIDGE OVER ROCK RUN)	FHWA 80% STATE 20% Y007-2A	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% Y007-2A	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% X028-2A
50104400	CONCRETE HEADWALL REMOVAL	EACH	5	3	2								
50200100	STRUCTURE EXCAVATION	CU YD	270			270							
50200300	COFFERDAM EXCAVATION	CU YD	55			55							
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	3			3							
50200500	COFFERDAMS	EACH	1			1							
50300225	CONCRETE STRUCTURES	CU YD	269.2			102.7	15.6		22.0	67.5	61.4		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	163.9			163.9							
50300260	BRIDGE DECK GROOVING	SQ YD	445			445							
50300280	CONCRETE ENCASEMENT	CU YD	4.2			4.2							
50400805	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 36 IN.	FOOT	695			695							
50800105	REINFORCEMENT BARS	POUND	74,970				1,110		3,070	10,690	6,650	14,750	38,700
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	43,450			43,450							
50800515	BAR SPLICERS	EACH	76			76							
51201600	FURNISHING STEEL PILES HP 12X53	FOOT	157.5			157.5							
51202305	DRIVING PILES	FOOT	157.5			157.5							
51203600	TEST PILE STEEL HP 12X53	EACH	2			2							
51204650	PILE SHOES	EACH	12			12							
51500100	NAME PLATES	EACH	19			1	7	1	6	1	1	1	1
52100540	ANCHOR BOLTS, 1 1/2"	EACH	4			4							
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	2				2						
54001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	1				1						
54001004	BOX CULVERT END SECTION, CULVERT NO. 4	EACH	2				2						
54001006	BOX CULVERT END SECTION, CULVERT NO. 6	EACH	1						1				
54001007	BOX CULVERT END SECTION, CULVERT NO. 7	EACH	2						2				
54001013	BOX CULVERT END SECTION, CULVERT NO. 13	EACH	2						2				
54001016	BOX CULVERT END SECTION, CULVERT NO. 16	EACH	2				2						
54001017	BOX CULVERT END SECTION, CULVERT NO. 17	EACH	6						6				
54001024	BOX CULVERT END SECTION, CULVERT NO. 24	EACH	2				2						
54002020	EXPANSION BOLTS 3/4 INCH	EACH	56				24		32				

\* DENOTES SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.P. ROUTE 505 (IL 75)

**SUMMARY OF QUANTITIES**

SCALE: VERT.  
HORIZ.  
DATE: 3/3/09

DRAWN BY MTH  
CHECKED BY SPF