

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
505	111RS-4, 111BR-1, Yc-15d-RS-1, & (W-15d)T-1	STEPHENSON & WINNEBAGO	335	9
STA.		TO STA.		
FED. ROAD DIST. NO. 2		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 64970				

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	STEPHENSON COUNTY	WINNEBAGO COUNTY	STEPHENSON COUNTY	STEPHENSON COUNTY	STEPHENSON COUNTY	WINNEBAGO COUNTY	WINNEBAGO COUNTY	WINNEBAGO COUNTY	WINNEBAGO COUNTY	WINNEBAGO COUNTY
				FHWA 80% STATE 20% 1000-2A	FHWA 80% STATE 20% 1000-2A	FHWA 80% STATE 20% X081-2A SN 089-0084 (BRIDGE OVER ROCK RUN)	FHWA 80% STATE 20% Y007-2A	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% Y007-2A	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% X028-2A
54003000	CONCRETE BOX CULVERTS	CU YD	195.8									82.7	113.1
54010404	PRECAST CONCRETE BOX CULVERT 4' X 4'	FOOT	33				14		19				
54010503	PRECAST CONCRETE BOX CULVERT 5' X 3'	FOOT	101				101						
54010505	PRECAST CONCRETE BOX CULVERT 5' X 5'	FOOT	106						106				
54010605	PRECAST CONCRETE BOX CULVERT 6' X 5'	FOOT	88				88						
54010606	PRECAST CONCRETE BOX CULVERT 6' X 6'	FOOT	88				88						
54010803	PRECAST CONCRETE BOX CULVERT 8' X 3'	FOOT	213					213					
54010804	PRECAST CONCRETE BOX CULVERT 8' X 4'	FOOT	80						80				
54010805	PRECAST CONCRETE BOX CULVERT 8' X 5'	FOOT	86						86				
54010907	PRECAST CONCRETE BOX CULVERT 9' X 7'	FOOT	136							136			
54011004	PRECAST CONCRETE BOX CULVERT 10' X 4'	FOOT	114							114			
54011006	PRECAST CONCRETE BOX CULVERT 10' X 6'	FOOT	104				104						
542A0241	PIPE CULVERTS, CLASS A, TYPE 1 36"	FOOT	90						90				
542A0247	PIPE CULVERTS, CLASS A, TYPE 1 42"	FOOT	9				9						
542A0253	PIPE CULVERTS, CLASS A, TYPE 1 48"	FOOT	25				25						
542A1093	PIPE CULVERTS, CLASS A, TYPE 2 48"	FOOT	108				108						
54200640	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"	FOOT	400		400								
54200643	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"	FOOT	48		48								
54200649	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 24"	FOOT	30		30								
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	5	1	4								
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	4		1				3				
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1				1						
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	4				4						
54248510	CONCRETE COLLAR	CU YD	7.3				3.5		3.8				
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	1,672	60	1,612								
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	35	35									
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	73			73							
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	142			142							
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	1	1									

DENOTES SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.P. ROUTE 505 (IL 75)

**SUMMARY OF QUANTITIES**

SCALE: VERT.  
HORIZ.  
DATE: 3/3/09

DRAWN BY MTH  
CHECKED BY SPF