

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
505	111RS-4, 111BR-1, Yo-15d-RS-1.& (W-15d)T-1	STEPHENSON & WINNEBAGO	335	10
STA.		TO STA.		
FED. ROAD DIST. NO. 2		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 64970				

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	STEPHENSON COUNTY	WINNEBAGO COUNTY	STEPHENSON COUNTY	STEPHENSON COUNTY	STEPHENSON COUNTY	WINNEBAGO COUNTY	WINNEBAGO COUNTY	WINNEBAGO COUNTY	WINNEBAGO COUNTY	WINNEBAGO COUNTY
				FHWA 80% STATE 20% 1000-2A	FHWA 80% STATE 20% 1000-2A	FHWA 80% STATE 20% X081-2A SN 089-0084 (BRIDGE OVER ROCK RUN)	FHWA 80% STATE 20% Y007-2A	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% Y007-2A	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% X028-2A
60242400	INLETS, SPECIAL	EACH	10		10								
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1									
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	19.9		19.9								
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2,607	43	2,564								
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	39	13	26								
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	323	159	164								
61100605	MISCELLANEOUS CONCRETE	CU YD	5		5								
61101009	STORM SEWERS PROTECTED, CLASS A, 8"	FOOT	150		150								
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	4		4								
61140000	STORM SEWERS, SPECIAL 8"	FOOT	200		200								
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1,362.5	1,087.5	275.0								
63100041	TRAFFIC BARRIER TERMINAL, TYPE 1B	EACH	3	3									
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2									
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4									
63100167	TRAFFIC BARRIER TERMINAL, TYPE I (SPECIAL) TANGENT	EACH	7	3	4								
63200310	GUARDRAIL REMOVAL	FOOT	4,225	3,025	1,200								
63500105	DELINEATORS	EACH	41	21	20								
66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1		1								
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	207	85	122								
66900665	TCL SOIL ANALYSIS	EACH	4		4								
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	12	6	6								
66900530	SOIL DISPOSAL ANALYSIS	EACH	1		1								
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	18	9.0	9.0								
67100100	MOBILIZATION	L SUM	1	0.5	0.5								
67201000	SEALING ABANDONED WATER WELLS	EACH	2		2								
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.5	0.5								
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.5	0.5								
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.5	0.5								
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1.0								
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	5	5								
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	24,998	12,167	12,831								
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,508		1,508								

* DENOTES SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 505 (IL 75)

SUMMARY OF QUANTITIES

SCALE: VERT. _____
HORIZ. _____
DATE: 3/3/09

DRAWN BY MTH
CHECKED BY SPF

PLOT DATE = 3/2/2009
FILE NAME = K:\11195800\11_75_3P_East\000\Design\195801_1500.dgn
SCALE = 1"=50'
USER NAME = SPF
MODEL = S00-6