

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
505	111RS-4, 111BR-1 Yc-15d-RS-1,& (W-15d)T-1	STEPHENSON & WINNEBAGO	335	12
STA.		TO STA.		
FED. ROAD DIST. NO. 2		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 64970				

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	STEPHENSON COUNTY	WINNEBAGO COUNTY	STEPHENSON COUNTY	STEPHENSON COUNTY	STEPHENSON COUNTY	WINNEBAGO COUNTY	WINNEBAGO COUNTY	WINNEBAGO COUNTY	WINNEBAGO COUNTY	WINNEBAGO COUNTY	STEPHENSON COUNTY
				FHWA 80% STATE 20% 1000-2A	FHWA 80% STATE 20% 1000-2A	FHWA 80% STATE 20% X081-2A	FHWA 80% STATE 20% Y007-2A	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% Y007-2A	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% X028-2A	COUNTY 50% STATE 50% Y002-2A
Z0025500	FURNISHING AND INSTALLING PROPERTY MARKERS	EACH	40	15	25									
Z0028415	GEOTECHNICAL REINFORCEMENT	SQ YD	5,711		5,711									
Z0040315	PILOT CAR	DAY	5	3	2									
Z0049800	RELOCATE EXISTING SURVEY MARKERS	EACH	20	5	15									
A2006514	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	10		10									
A2006714	TREE, QUERCUS MACROCARPA (BUR OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	15	10	5									
A2007814	TREE, TILIA AMERICANA (AMERICAN LINDEN/BASSWOOD), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	15	10	5									
B2000562	TREE, AMELANCHIER CANADENSIS (SHADBLOW SERVICEBERRY), 4' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	24	10	14									
B2004514	TREE, MALUS RED JEWEL (RED JEWEL CRAB APPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	25	10	15									
B2004814	TREE, MALUS SARGENTII (SARGENT CRABAPPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	30	10	20									
C2001748	SHRUB, CORNUS SERICEA (CARDINAL REDOSIER DOGWOOD), 4' HEIGHT, BALLED AND BURLAPPED	EACH	50		50									
D2002272	EVERGREEN, PICEA PUNGENS GLAUCA (COLORADO BLUE SPRUCE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	15		15									
D2003172	EVERGREEN, PSUEDOTSUGA MENZIESII (DOUGLAS FIR), 6' HEIGHT, BALLED AND BURLAPPED	EACH	10		10									
X0322352	SEEDING MOBILIZATION	EACH	13	8	5									
X0324066	SLOPED METAL END SECTION WITH GRATE, 24 INCH	EACH	2		2									
X0325359	SLOPED METAL END SECTION WITH GRATE, 18 INCH	EACH	2		2									
X0325519	DRAIN FOR AGGREGATE BASE COURSE	SQ YD	19		19									
X0325665	SLOPED METAL END SECTION WITH GRATE, 15 INCH	EACH	16		16									
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	501	501										
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1	0.5	0.5									
XX005938	SOLAR-POWERED FLASHING BEACON ASSEMBLY (COMPLETE)	EACH	6											6
31100950	SUB-BASE GRANULAR MATERIAL, TYPE A 21"	SQ YD	10,800		10,800									

• DENOTES SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 505 (IL 75)

SUMMARY OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE: 3/3/09

DRAWN BY MTH
CHECKED BY SPF