

EARTHWORK SCHEDULE		TOPSOIL EXCAVATION AND PLACEMENT	EARTH EXCAVATION	TOPSOIL TO BE REUSED (ADJ FOR 25% SHRINKAGE)	EXCAVATION TO BE USED IN EMBANKMENT (ADJ FOR 25% SHRINKAGE)	TOPSOIL REQUIRED	EMBANKMENT REQUIRED	TOPSOIL BALANCE WASTE (+) OR SHORTAGE (-)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE, 6"
		21101505 CU YD	20200100 CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
STEPHENSON COUNTY	CULVERT #17 Sta. 10446+50 to 10451+00	341	592	256	444	424	350	-168	94	1,010
	CULVERT #24 Sta. 10581+00 to 10586+50	271	82	203	62	339	799	-136	-738	815
	GUARDRAIL #1 Sta. 10635+70 to 10639+00	85	88	64	66	15	128	49	-62	-293
	CULVERT #16 Sta. 10653+00 to 10658+00	366	519	275	389	474	761	-200	-372	1,197
	CULVERT #1 Sta. 10667+00 to 10673+50	845	6,779	634	5,084	1,238	2,152	-604	2,932	3,626
	BRIDGE OVER ROCK RUN Sta. 10698+00 to 10715+00	611	476	458	357	508	1,318	-50	-961	299
	CULVERT #4 Sta. 10765+00 to 10770+00	465	265	349	199	673	2,723	-324	-2,524	1,946
	CULVERT #5 Sta. 10811+50 to 10815+50	310	1,773	233	1,330	441	326	-209	1,004	1,251
	CEDARVILLE ROAD @ IL-75	224	1,545	168	1,159	223	61	-55	1,098	330
	STEPHENSON COUNTY TOTAL	3,518	12,119	2,639	9,089	4,335	8,618	-1,697	471	10,179
WINNEBAGO COUNTY	CULVERT #6 Sta. 10851+00 to 10857+00	332	336	249	252	465	899	-216	-647	1,296
	CULVERT #7 Sta. 10891+00 to 10898+50	636	1,082	477	812	902	1,858	-425	-1,047	2,550
	CULVERT #8 Sta. 10966+00 to 10971+50	535	840	401	630	748	1,330	-347	-700	2,081
	CULVERT #14 Sta. 11052+50 to 11056+50	280	917	210	688	349	262	-139	426	834
	CULVERT #15 Sta. 11073+00 to 11077+50	374	1,139	281	854	460	850	-180	4	1,077
	RECONSTRUCTION IL-75 Sta. 10988+00 to 11028+50	4,204	46,152	3,153	34,614	4,566	27,187	-1,413	7,427	8,478
	RECONSTRUCTION IL-70 Sta. 97+50 to 116+30	1,555	11,563	1,166	8,672	1,552	864	-386	7,808	2,315
	LEECH ROAD @ IL-70	25	61	19	46	28	53	-9	-7	56
	LEECH ROAD @ IL-75	212	1,360	159	1,020	179	124	-20	896	120
	LEECH ROAD @ FRITZ ROAD	64	444	48	333	72	23	-24	310	144
WINNEBAGO COUNTY TOTAL	8,217	63,894	6,163	47,921	9,321	33,450	-3,158	14,471	18,950	
GRAND TOTAL	11,735	76,013	8,801	57,010	13,656	42,068	-4,855	14,942	29,129	

PLOT DATE = 3/2/09
FILE NAME = K:\11156800\1175_3p_earth\work\design\1156800L_Schedule.dgn
PLOT SCALE = 1/8"=1'-0"
USER NAME = JTracy
MODEL = Earthwork

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 505 (IL 75)

EARTHWORK SCHEDULE

VERT. SCALE: 3/3/09
HORIZ. SCALE: 1"=100'
DATE: 3/3/09

DRAWN BY MTH
CHECKED BY SPF