

CULVERT SCHEDULE	REMOVAL OF EXISTING STRUCTURES	CONCRETE HEADWALL REMOVAL		NAME PLATES	BOX CULVERT END SECTION		CONCRETE BOX CULVERTS	PRECAST CONCRETE BOX CULVERT 4' X 4'	PRECAST CONCRETE BOX CULVERT 5' X 3'	PRECAST CONCRETE BOX CULVERT 5' X 5'	PRECAST CONCRETE BOX CULVERT 6' X 5'	PRECAST CONCRETE BOX CULVERT 6' X 6'	PRECAST CONCRETE BOX CULVERT 8' X 3'	PRECAST CONCRETE BOX CULVERT 8' X 4'	PRECAST CONCRETE BOX CULVERT 8' X 5'	PRECAST CONCRETE BOX CULVERT 9' X 7'	PRECAST CONCRETE BOX CULVERT 10' X 4'	PRECAST CONCRETE BOX CULVERT 10' X 6'
	50100300 - 50101429	50104400	51500100	54001001-54001024	54003000	54010404	54010503	54010505	54010605	54010606	54010803	54010804	54010804	54010805	54010907	54011004	54011006	
	EACH	EACH		EACH	EACH		CU YD	FOOT		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	
		LT	RT		LT	RT		LT	RT									
STEPHENSON COUNTY																		
CULVERT #17 (SN 089-1090) Sta. 10448+72	1			1	3	3							213					
CULVERT #24 (SN 089-1091) Sta. 10583+97	1			1	1	1						88						
CULVERT #16 (SN 089-1092) Sta. 10655+40	1			1	1	1			101									
CULVERT #1 (SN 089-1100) Sta. 10670+72	1			1	1	1				88								
CULVERT #2 (SN 089-1069) Sta. 10710+42		1	1	1		1		6.0	8.0									
CULVERT #3 (SN 089-1094) Sta. 10714+46		1		1														
CULVERT #4 (SN 089-1101) Sta. 10767+68	1			1	1	1												104
CULVERT #5 (SN 089-1093) Sta. 10813+56 FIELD ACCESS Sta. 10813+56	1			1														
STEPHENSON COUNTY TOTAL	6	3		8	15		0	14.0	101	0	88	88	213	0	0	0	0	104
WINNEBAGO COUNTY																		
CULVERT #6 (SN 101-1094) Sta. 10854+01	1			1	1					106								
CULVERT #7 (SN 101-1320) Sta. 10894+20	1			1	1	1									86			
CULVERT #8 (SN 101-2048) Sta. 10968+79	1			1												136		
CULVERT #9 (SN 101-1088) Sta. 10990+83				1														
CULVERT #10 (SN 101-1319) Sta. 10998+25	1			1									80					
CULVERT #11 (SN 101-2049) Sta. 11025+71	1			1													114	
CULVERT #12 (SN 101-1089) Sta. 109+39	1			1														
CULVERT #13 (SN 101-1051) Sta. 114+42		1	1	1	1	1		9.0	10.0									
CULVERT #14 (SN 101-1083) Sta. 11054+39	1			1			82.7											
CULVERT #15 (SN 101-1082) Sta. 11075+29.29	1			1			113.1											
WINNEBAGO COUNTY TOTAL	8	2		10	5		195.8	19.0	0	106	0	0	0	80	86	136	114	0
GRAND TOTAL	14	5		18	20		196	33.0	101	106	88	88	213	80	86	136	114	104

SEE BILL OF MATERIALS ON CULVERT DETAIL SHEETS FOR ADDITIONAL PAY ITEMS AND QUANTITIES

PLOT DATE = 3/3/2009  
FILE NAME = K:\11196800\1.75.3p\_east\cadd\design\195801\_Schedule.01.dgn  
PLOT SCALE = 1:80  
USER NAME = JTracy  
MODEL = Culvert 1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.P. ROUTE 505 (IL 75)

**CULVERT SCHEDULE**  
**(1 OF 2)**

SCALE: VERT.     DRAWN BY MTH  
HORIZ.            CHECKED BY SPF  
DATE: 3/3/09