

CULVERT SCHEDULE	PIPE CULVERTS, CLASS A, TYPE 1 36"		PIPE CULVERTS, CLASS A, TYPE 1 42"		PIPE CULVERTS, CLASS A, TYPE 1 48"	PIPE CULVERTS, CLASS A, TYPE 2 48"	REINFORCED CONCRETE FLARED END SECTIONS 36"		REINFORCED CONCRETE FLARED END SECTIONS 42"		REINFORCED CONCRETE FLARED END SECTIONS 48"		REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL*		BREAKER-RUN CRUSHED STONE*		STONE RIPRAP, CLASS A4		FILTER FABRIC		CULVERT TO BE CLEANED	
	542A0241		542A0247		542A0253	542A1093	54213681		54213687		54213693		20201200		Z0005400		28100107		28200200		Z0014800	
	FOOT		FOOT		FOOT	FOOT	EACH		EACH		EACH		CU YD		TON		SQ YD		SQ YD		FOOT	
	LT	RT	LT	RT			LT	RT	LT	RT	LT	RT	LT	RT	LT	RT	LT	RT	LT	RT		
STEPHENSON COUNTY																						
CULVERT #17 (SN 089-1090) Sta. 10448+72													82.2	82.2	108.9	108.9	78.4	59.3	78.4	59.3		
CULVERT #24 (SN 089-1091) Sta. 10583+97													39.0	39.0	51.7	51.7	6.6	14.1	6.6	14.1		
CULVERT #16 (SN 089-1092) Sta. 10655+40													94.3	94.3	125.2	125.2	35.2	34.7	35.2	34.7		
CULVERT #1 (SN 089-1100) Sta. 10670+72													66.9		88.8		11.1	11.1	11.1	11.1		
CULVERT #2 (SN 089-1069) Sta. 10710+42													8.2	8.2	10.7	10.9					62	
CULVERT #3 (SN 089-1094) Sta. 10714+46				9.0						1				9.9		13.0					67	
CULVERT #4 (SN 089-1101) Sta. 10767+68													103.5		137.4		31.7	48.9	31.7	48.9		
CULVERT #5 (SN 089-1093) Sta. 10813+56						108.0					1	1	65.9		87.4		12.3	6.1	12.3	6.1		
FIELD ACCESS Sta. 10813+56					25.0						1	1										
STEPHENSON COUNTY TOTAL	0.0		9.0		25.0	108.0	0		1		4		694		920		350		350		129	
WINNEBAGO COUNTY																						
CULVERT #6 (SN 101-1094) Sta. 10854+01													69.5		96.3							
CULVERT #7 (SN 101-1320) Sta. 10894+20													75.9		100.7		16.0	39.2	16.0	39.2		
CULVERT #8 (SN 101-2048) Sta. 10968+79													176.3		248.3		68.9	31.2	68.9	31.2		
CULVERT #9 (SN 101-1088) Sta. 10990+83	9.0	10.0					1	1					9.7	7.9	12.6	8.1	11.9	12.2	11.9	12.2		
CULVERT #10 (SN 101-1319) Sta. 10998+25													87.5		121.3		37.0	11.6	37.0	11.6		
CULVERT #11 (SN 101-2049) Sta. 11025+71													161.7		214.6		18.1	27.8	18.1	27.8		
CULVERT #12 (SN 101-1089) Sta. 109+39	71.0							1					41.5		55.0		5.9		5.9			
CULVERT #13 (SN 101-1051) Sta. 114+42													8.8	8.8	11.6	11.6	7.3	28.9	7.3	28.9	65	
CULVERT #14 (SN 101-1083) Sta. 11054+39													369.0		683.0		103.0		103.0			
CULVERT #15 (SN 101-1082) Sta. 11075+29.29													498.0		921.0		84.0		84.0			
WINNEBAGO COUNTY TOTAL	90.0		0.0		0.0	0.0	3		0		0		1,515		2,484		503		503		65	
GRAND TOTAL	90.0		9.0		25.0	108.0	3		1		4		2,208		3,404		853		853		194	

SEE BILL OF MATERIALS ON CULVERT DETAIL SHEETS FOR ADDITIONAL PAY ITEMS AND QUANTITIES

PLOT DATE = 3/3/09
FILE NAME = K:\11195600\1.75.3p east\cadd\design\195801_Schedules.dwg
PLOT SCALE = 1:50
USER NAME = JTracy
MODEL = Culvert 2

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 505 (IL 75)

**CULVERT SCHEDULE
(2 OF 2)**

SCALE: VERT.
HORIZ.
DATE: 3/3/09

DRAWN BY MTH
CHECKED BY SPF