

GUARDRAIL SCHEDULE				STEEL PLATE BEAM GUARDRAIL, TYPE A	TRAFFIC BARRIER TERMINAL TYPE 1B	TRAFFIC BARRIER TERMINAL TYPE 2	TRAFFIC BARRIER TERMINAL TYPE 6	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	GUARDRAIL REMOVAL	GUARDRAIL MARKERS - TYPE A	BARRIER WALL MARKERS - TYPE B	TERMINAL MARKER-DIRECT APPLIED
				63000000	63100041	63100045	63100085	63100167	63200310	78200410	78200520	78201000
				FOOT	EACH	EACH	EACH	EACH	FOOT	EACH	EACH	EACH
STEPHENSON COUNTY	CULVERT #17 (SN 089-1090)	RT	10447+00.00	10448+87.00					187.5			
		LT	10448+17.00	10449+55.00					137.5			
	CULVERT #24 (SN 089-1091)	LT	10582+28.50	10586+28.50					400.0			
		RT	10583+22.50	10585+72.50					250.0			
	GUARDRAIL #1	RT	10635+90.00	10638+15.00					225.0			
		RT	10636+40.00	10637+89.00	150.0						4	2
	CULVERT #16 (SN 089-1092)	LT	10654+78.00	10655+78.00					100.0			
		RT	10655+05.00	10656+05.00					100.0			
	CULVERT #1 (SN 089-1100)	LT	10669+85.00	10671+85.00					200.0			
		RT	10669+65.00	10671+65.00					200.0			
	BRIDGE OVER ROCK RUN	LT	10703+96.00	10704+96.00					100.0			
		RT	10703+96.00	10704+96.00					100.0			
		LT	10705+82.00	10707+07.00					125.0			
		RT	10705+82.00	10707+07.00					125.0			
		RT	10702+13.50	10703+26.00	137.5	1	1				2	
		LT	10703+87.00	10704+37.00	50.0			1	1		2	1
		RT	10704+12.00	10704+37.00	50.0		1	1			1	
	BRIDGE PARAPET	LT	10704+79.69	10705+97.53								1
BRIDGE PARAPET	RT	10704+79.69	10705+97.53								2	
	LT	10706+40.00	10708+02.50	162.5	1		1			3		
	RT	10706+40.00	10711+77.50	537.5	1		1			8		
CULVERT #4 (SN 089-1101)	LT	10766+66.00	10769+16.00						250.0			
	RT	10765+86.00	10769+11.00						325.0			
CULVERT #5 (SN 089-1093)	LT	10813+19.00	10814+19.00						100.0			
	RT	10813+97.00	10814+97.00						100.0			
STEPHENSON COUNTY TOTAL				1087.5	3	2	4	3	3025.0	20	3	3
WINNEBAGO COUNTY	CULVERT #6 (SN 101-1094)	LT	10853+75.00	10854+75.00					100.0			
		RT	10853+02.50	10854+52.50					150.0			
	CULVERT #7 (SN 101-1320)	LT	10893+25.00	10895+75.00					250.0			
		RT	10853+58.00	10854+58.00					100.0			
	CULVERT #8 (SN 101-2048)	LT	10968+29.00	10969+29.00					100.0			
		RT	10968+29.00	10969+29.00					100.0			
	CULVERT #10 (SN 101-1319)	LT	10997+77.00	10998+77.00					100.0			
		RT	10997+77.00	10998+77.00					100.0			
	CULVERT #15 (SN 101-1082)	LT	11075+20.00	11076+20.00					100.0			
		RT	11074+85.00	11075+85.00					100.0			
LEECH ROAD DETOUR	LT			137.5				2			2	
ø 96" CULVERT	RT			137.5				2			2	
WINNEBAGO COUNTY TOTAL				275.0	0	0	0	4	1200.0	8	0	4
GRAND TOTAL				1362.5	3	2	4	7	4225.0	28	3	7

ESTIMATED PAY ITEMS			
		UNIT	TOTAL
20200410	EARTH EXCAVATION (SPECIAL)	CU YD	10
40600525	LEVELING BINDER (HAND METHOD), N50	TON	10
40600895	CONSTRUCTING TEST STRIP	EACH	2
40702700	FURNISH PROFILOGRAPH	L SUM	1
61100605	MISCELLANEOUS CONCRETE	CU YD	5
61101009	STORM SEWERS PROTECTED, CLASS A, 8"	FT	150
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	4
61140000	STORM SEWERS (SPECIAL) 8"	FT	200
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	12
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	18
67100100	MOBILIZATION	L SUM	1
67201000	SEALING ABANDONED WATER WELLS	EACH	2
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0020900	ESTABLISHING AND REFERENCING LAND SECTION MARKERS	EACH	1
Z0025500	FURNISHING AND INSTALLING PROPERTY MARKERS	EACH	40
Z0040315	PILOT CAR	DAY	5
Z0049800	RELOCATE EXISTING SURVEY MARKERS	EACH	20
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1

BUILDING REMOVAL SCHEDULE			
BUILDING	COUNTY	STATION	OFFSET (FT)
BUILDING REMOVAL, NO. 1 Z0007601	STEPHENSON	10766+00.00	40 RT.
BUILDING REMOVAL, NO. 2 Z0007602	WINNEBAGO	10999+50.00	60 LT.
BUILDING REMOVAL, NO. 3 Z0007603	WINNEBAGO	11011+00.00	57 LT.
BUILDING REMOVAL, NO. 4 Z0007604	WINNEBAGO	11012+25.00	77 RT.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.P. ROUTE 505 (IL 75)
NAME	DATE	
		GUARDRAIL & BUILDING REMOVAL SCHEDULES SCALE: VERT. DRAWN BY MTH HORIZ. CHECKED BY SPF DATE: 3/3/09

NOTE: THERE IS THE POTENTIAL FOR CROSS-R.O.W. FIELD TILE AT THE RECONSTRUCTION AROUND THE INTERSECTION OF IL RTE. 75 AND IL RTE. 70 IN WINNEBAGO COUNTY. QUANTITIES ARE ESTIMATED FOR TWO CROSSING FIELD TILES.

PLOT DATE = 3/2/2009
FILE NAME = H:\11565820\1_75_3p_east\cadd\design\96801\Schedule.dwg
PLOT SCALE = 1/8"=1'-0"
USER NAME = JTracey
MODEL = Guardrail_BldgRem