F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
505	111RS-4, 111BR-1, Ya-15d-RS-1.& (W-15d)T-1	STEPHENSON & WINNEBAGO	335	28
STA.		TO STA.		
FED. ROAD DIST. NO. 2	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 64970

25100900 TURF REINFORCEMENT MAT

SQ YD	LOCATION			
	STEPHENSON COUNTY		IL RTE. 75	
77	RT STA	10449+54.00	-	10450+69.00
200	LT STA	10445+50.00	-	10448+50.00
114	LT STA	10449+00.00	-	10450+71.00
100	LT STA	10583+50.00	-	10585+00.00
133	LT STA	10655+50.00	-	10657+50.00
150	LT STA	10670+75.00	-	10673+00.00
27	LT STA	10710+00.00	-	10710+40.00
145	LT STA	10765+75.00	-	10767+93.00
24	RT STA	10765+25.00	-	10766+25.00
24	RT STA	10767+70.00	-	10768+50.00
24	RT STA	10812+00.00		10812+50.00
	WINNEBAGO COUNTY		IL RTE. 75	
133	RT STA	10854+25.00	-	10856+25.00
150	RT STA	10894+25.00	-	10896+50.00
83	LT STA	10894+25.00	-	10895+50.00
100	RT STA	10966+50.00	-	10968+00.00
100	RT STA	10969+50.00	-	10971+00.00
143	LT STA	10966+50.00	-	10968+65.00
105	LT STA	10968+92.00	-	10970+50.00
467	RT STA	10991+00.00	-	10998+00.00
180	RT STA	10998+30.00	-	11001+00.00
307	RT STA	11021+00.00	-	11025+60.00
150	RT STA	11026+00.00	-	11028+25.00
100	LT STA	10993+00.00	-	10994+50.00
33	LT STA	11003+50.00	-	11004+00.00
67	LT STA	11023+00.00	-	11024+00.00
100	LT STA	11026+50.00	-	11028+00.00
166	RT STA	11053+00.00	-	11055+49.00
83	LT STA	11053+00.00	-	11054+25.00
97	LT STA	11054+55.00	-	11056+00.00
233	RT STA	11073+50.00	-	11077+00.00
133	LT STA	11073+50.00	-	11075+50.00
87	LT STA	11075+70.00	-	11077+00.00
	WINNEBAGO COUNTY		IL RTE. 70	
550	RT STA	97+75.00	-	106+00.00
483	LT STA	97+75.00	-	105+00.00
233	RT STA	110+50.00	-	114+00.00
67	LT STA	109+00.00	-	110+00.00
260	LT STA	110+50.00	-	114+40.00
5629	TOTAL			

28000250 TEMPORARY EROSION CONTROL SEEDING

POUNDS	LOCATION			
	STEPHENSON COUNTY		IL RTE. 75	
117.7	LT STA	10445+00	-	10448+72
89.3	LT STA	10448+72	-	10451+00
108.4	RT STA	10446+00	-	10448+72
115.0	RT STA	10448+72	-	10450+80
144.5	LT STA	10581+00	-	10586+00
28.0	RT STA	10581+50	-	10583+05
165.2	RT STA	10583+05	-	10586+50
7.8	RT STA	10638+50	-	10639+00
244.9	LT STA	10653+00	-	10659+00
237.0	RT STA	10653+00	-	10659+00
737.5	LT STA	10667+00	-	10673+50
387.0	RT STA	10667+00	-	10673+50
40.1	LT STA	10702+00	-	10705+00
92.3	RT STA	10698+00	-	10703+75
29.1	RT STA	10703+75	-	10705+00
67.9	RT STA	10705+50	-	10708+00
82.7	RT STA	10710+00	-	10715+00
251.7	LT STA	10705+50	-	10714+50
283.6	LT STA	10765+50	-	10769+50
349.3	RT STA	10765+00	-	10770+00
142.3	LT STA	10811+50	-	10816+50
35.6	LT STA	FIELD CULVERT	-	
273.3	RT STA	10813+50	-	10816+50
1619.2	TURF SHOULDERS			
	STEPHENSON COUNTY		CEDARVILLE RD & IL RTE. 75	
40.7	NE QUAD			
148.1	SE QUAD			

28000250 TEMPORARY EROSION CONTROL SEEDING, CONT.

	WINNEBAGO COUNTY		IL RTE. 75	
217.4	LT STA	10851+00	-	10857+00
299.2	RT STA	10851+00	-	10857+00
412.2	LT STA	10891+00	-	10898+50
441.7	RT STA	10891+50	-	10898+50
399.4	LT STA	10966+00	-	10971+50
280.1	RT STA	10966+00	-	10971+50
649.7	LT STA	10988+00	-	11001+40
835.7	LT & RT STA	11001+40	-	97+50
948.5	LT & RT STA	10988+00	-	109+46
1113.9	LT & RT STA	97+50	-	11012+46
440.3	LT & RT STA	108+50	-	11011+22
247.5	RT STA	11011+22	-	11013+32
198.2	RT STA	11013+32	-	11015+22
209.9	LT STA	11012+46	-	11015+46
787.9	RT STA	11015+22	-	11028+50
697.5	LT STA	11015+46	-	11028+50
72.1	LT STA	11052+50	-	11054+39
76.4	LT STA	11054+39	-	11056+50
74.2	RT STA	11052+50	-	11054+39
71.0	RT STA	11054+39	-	11056+50
121.7	LT STA	11073+00	-	11075+30
112.1	LT STA	11075+30	-	11077+50
94.7	RT STA	11073+00	-	11075+30
100.4	RT STA	11075+30	-	11077+50
1472.0	TURF SHOULDERS			
	WINNEBAGO COUNTY		IL RTE. 70	
61.8	LT STA	108+80	-	110+20
326.3	LT STA	110+40	-	116+30
25.3	RT STA	109+46	-	110+18
51.2	RT STA	110+18	-	111+50
166.8	RT STA	111+50	-	115+30
20.6	RT STA	115+40	-	116+30
	WINNEBAGO COUNTY		LEECH RD & IL RTE. 70	
40.1	NE QUAD			
	WINNEBAGO COUNTY		LEECH RD & IL RTE. 75	
40.6	NE QUAD			
28.0	SE QUAD			
51.7	SW QUAD			
60.1	NW QUAD			
	WINNEBAGO COUNTY		LEECH RD & FRITZ RD	
68.2	NE QUAD			
17153	TOTAL			

28000300 TEMPORARY DITCH CHECKS

EACH	LOCATION			
	STEPHENSON COUNTY		IL RTE. 75	
13	LT STA	10445+50.00	-	10448+50.00
3	LT STA	10449+00.00	-	10450+50.00
3	RT STA	10449+25.00	-	10450+75.00
17	LT STA	10581+50.00	-	10585+50.00
7	RT STA	10582+50.00	-	10584+00.00
13	LT STA	10654+50.00	-	10657+50.00
13	RT STA	10667+50.00	-	10670+50.00
12	LT STA	10667+75.00	-	10670+50.00
5	LT STA	10671+00.00	-	10673+00.00
5	LT STA	10703+50.00	-	10704+50.00
17	LT STA	10710+00.00	-	10714+00.00
12	RT STA	10710+25.00	-	10713+00.00
4	RT STA	10765+75.00	-	10766+50.00
4	LT STA	10766+75.00	-	10767+50.00
7	RT STA	10768+00.00	-	10769+50.00
11	RT STA	10812+00.00	-	10814+50.00
	STEPHENSON COUNTY		CEDARVILLE & IL RTE. 75	
2	NE QUAD	10383+25.00		10384+00.00
6	SE QUAD	220+00.00		222+50.00

28000300 TEMPORARY DITCH CHECKS, CONT.

5	LT STA	10854+00.00	-	10856+00.00
17	RT STA	10892+50.00	-	10896+50.00
7	LT STA	10894+50.00	-	10896+00.00
7	RT STA	10966+50.00	-	10971+00.00
7	LT STA	10966+50.00	-	10971+00.00
6	RT STA	10991+00.00	-	10998+00.00
3	LT STA	10993+00.00	-	10996+00.00
5	RT STA	10998+25.00	-	11001+00.00
8	RT STA	11003+50.00	-	11005+25.00
2	LT STA	11003+50.00	-	11003+75.00
13	RT STA	11018+00.00	-	11021+00.00
20	LT STA	11018+00.00	-	11022+75.00
9	RT STA	11021+50.00	-	11025+50.00
4	RT STA	11026+00.00	-	11027+50.00
4	LT STA	11026+00.00	-	11028+00.00
5	RT STA	11053+00.00		11056+00.00
5	LT STA	11053+00.00		11056+00.00
8	RT STA	11073+50.00		11077+00.00
8	LT STA	11073+50.00		11077+00.00
	WINNEBAGO COUNTY		IL RTE. 70	
14	LT STA	98+00.00		104+50.00
11	LT STA	109+00.00	-	114+00.00
7	LT STA	114+50.00	-	116+00.00
16	RT STA	98+00.00	-	105+50.00
3	RT STA	112+00.00	-	113+50.00
8	RT STA	114+50.00	-	116+30.00
	WINNEBAGO COUNTY		LEECH RD & IL RTE. 70	
3	NE QUAD			
	WINNEBAGO COUNTY		LEECH RD & IL RTE. 75	
4	NW QUAD			
4	SW QUAD			
3	SE QUAD			
	WINNEBAGO COUNTY		LEECH RD & FRITZ RD	
3	NE QUAD			
373	TOTAL			

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 505 (IL 75)

QUANTITY SCHEDULES

SCALE: VERT. HORIZ.
DATE: 3/3/09
DRAWN BY MTH
CHECKED BY SPF

PLOT DATE = 3/4/2009
FILE NAME = K:\1195808\IL 75_3P East\CADD\Design\195808L_Schedules_all.dgn
PLOT SCALE = 1:50
USER NAME = Timothy
MODEL = Quantity Schedules4