

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
505	111RS-4, 111BR-1, Yg-15d-RS-1, & (W-15d)T-1	STEPHENSON & WINNEBAGO	335	35
STA.		TO STA.		
FED. ROAD DIST. NO. 2		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 64970				

78100100 RAISED REFLECTIVE PAVEMENT MARKER, CONT.

WINNEBAGO COUNTY		IL-75 @ IL-70	
AMBER			
6	(40' oc)	(AMBER) TWO-WAY	10996+33.00 - 10997+13.00
22	(40' oc)	(AMBER) TWO-WAY	10997+53.00 - 11006+00.00
43	(20' oc)	(AMBER) TWO-WAY	10997+53.00 - 11006+00.00
49	(20' oc)	(AMBER) TWO-WAY	11007+25.00 - 11016+85.00
25	(40' oc)	(AMBER) TWO-WAY	11007+25.00 - 11016+85.00
6	(40' oc)	(AMBER) TWO-WAY	11017+32.00 - 11018+12.00
CRYSTAL			
15	(20' oc)	(CRYSTAL) ONE-WAY	11003+11.00 - 11006+00.00
15	(20' oc)	(CRYSTAL) ONE-WAY	11003+11.00 - 11006+00.00
20	(20' oc)	(CRYSTAL) ONE-WAY	11007+25.00 - 11011+20.00
20	(20' oc)	(CRYSTAL) ONE-WAY	11007+25.00 - 11011+20.00
WINNEBAGO COUNTY		IL-70 @ IL-75	
AMBER			
23	(40' oc)	(AMBER) TWO-WAY	97+50.00 - 106+44.00
45	(20' oc)	(AMBER) TWO-WAY	97+50.00 - 106+44.00
44	(20' oc)	(AMBER) TWO-WAY	107+56.00 - 116+30.00
22	(40' oc)	(AMBER) TWO-WAY	107+56.00 - 116+30.00
CRYSTAL			
15	(20' oc)	(CRYSTAL) ONE-WAY	103+34.00 - 106+31.00
17	(20' oc)	(CRYSTAL) ONE-WAY	103+34.00 - 106+54.00
14	(20' oc)	(CRYSTAL) ONE-WAY	107+46.00 - 110+21.00
755	TOTAL		

Z0022800 FENCE REMOVAL

FOOT	LOCATION	IL-75
STEPHENSON COUNTY		
75	RT STA	10583+15.00 - 10583+90.00
125	RT STA	10584+35.00 - 10585+60.00
325	RT STA	10766+50.00 - 10769+75.00
185	LT STA	10765+25.00 - 10767+10.00
WINNEBAGO COUNTY		
500	RT STA	10851+50.00 - 10856+50.00
270	LT STA	10965+75.00 - 10968+45.00
135	LT STA	10970+20.00 - 10971+55.00
355	RT STA	10990+00.00 - 10993+55.00
40	RT STA	10993+55.00 - 10993+55.00
445	RT STA	10993+55.00 - 10998+00.00
250	RT STA	10999+80.00 - 11002+30.00
55	RT STA	10999+80.00 - 11002+30.00
300	RT STA	11002+60.00 - 11005+60.00
90	RT STA	11005+61.00 - 11005+61.00
45	RT STA	11011+37.00 - 11011+37.00
45	RT STA	11013+17.00 - 11013+17.00
300	LT STA	11012+45.00 - 11015+45.00
45	LT STA	11012+45.00 - 11012+45.00
37	LT STA	11013+00.00 - 11013+00.00
30	LT STA	11013+70.00 - 11013+70.00
25	LT STA	11015+45.00 - 11015+45.00
450	RT STA	11023+90.00 - 11028+40.00
37	RT STA	11023+90.00 - 11023+90.00
115	RT STA	108+00.00 - 109+15.00
225	RT STA	11052+00.00 - 11054+25.00
209	RT STA	11054+60.00 - 11056+69.00
265	RT STA	11072+75.00 - 11075+40.00
175	RT STA	11075+75.00 - 11077+50.00
35	RT STA	11075+95.00 - 11075+95.00
250	LT STA	11072+75.00 - 11075+25.00
30	LT STA	11073+55.00 - 11073+55.00
190	LT STA	11075+85.00 - 11077+75.00
50	LT STA	11076+10.00 - 11076+10.00
WINNEBAGO COUNTY		
80	NE QUAD	IL-70 @ LEECH RD
WINNEBAGO COUNTY		
260	NW QUAD	IL-75 @ LEECH RD
150	SW QUAD	IL-75 @ LEECH RD
6198	TOTAL	

X6063600 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24

FOOT	LOCATION	IL-75
STEPHENSON COUNTY		
501.4	STA	10698+50.00 - 10703+51.40
501	TOTAL	

X0325519 DRAIN FOR AGGREGATE BASE COURSE

SQ YD	LOCATION	IL-75
WINNEBAGO COUNTY		
3.33	STA	10994+50.00 - 10994+50.00
2.67	STA	11005+75.00 - 11005+75.00
3.33	STA	11027+50.00 - 11027+50.00
WINNEBAGO COUNTY		
4.00	STA	98+00.00 - 98+00.00
2.67	STA	102+00.00 - 102+00.00
3.33	STA	111+00.00 - 111+00.00
19	TOTAL	

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

EACH	LOCATION	IL-75 @ BEST RD
WINNEBAGO COUNTY		
20	(40' oc)	10860+75.00 - 10864+50.00
28	(40' oc)	10864+50.00 - 10875+30.00
55	(20' oc)	10864+50.00 - 10875+30.00
19	(20' oc)	10871+70.00 - 10875+30.00
14	(20' oc)	10876+40.00 - 10879+00.00
9	(20' oc)	10876+40.00 - 10878+00.00
41	(20' oc)	10876+40.00 - 10884+40.00
21	(40' oc)	10876+40.00 - 10884+40.00
10	(40' oc)	10884+40.00 - 10886+00.00
WINNEBAGO COUNTY		IL-75 @ PECATONICA RD
44	(40' oc)	10911+50.00 - 10920+00.00
22	(40' oc)	10920+00.00 - 10928+40.00
43	(20' oc)	10920+00.00 - 10928+40.00
12	(20' oc)	10926+20.00 - 10928+40.00
8	(20' oc)	10929+20.00 - 10930+60.00
35	(20' oc)	10929+20.00 - 10936+15.00
18	(40' oc)	10929+20.00 - 10936+15.00
30	(40' oc)	10936+15.00 - 10942+00.00
429	TOTAL	

X0322352 SEEDING MOBILIZATION

EACH	LOCATION
STEPHENSON COUNTY	
1	YEAR ONE DETOUR INTERSECTION & DETOUR IMPROVEMENTS
1	CULVERT #17
1	CULVERT #24
1	GUARDRAIL IMPROVEMENT SITE
1	CULVERT #1
1	BRIDGE OVER ROCK RUN CREEK & CULVERT #16
1	CULVERT #4
1	CULVERT #5
WINNEBAGO COUNTY	
1	CULVERTS #6 & #7
1	CULVERT #8
1	IL 75/IL 70 RECONSTRUCTION & CULVERTS #9, #13, & #15
1	CULVERT #14
1	YEAR TWO DETOUR INTERSECTION & DETOUR IMPROVEMENTS
13	TOTAL

PLOT DATE = 2/4/2009
FILE NAME = K:\1195800\IL 75.sp East\CADD\Design\98881\Sched\loc.all.dgn
PLOT SCALE = 1:50
USER NAME = JFrasney
MODEL = Quantity Schedule1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 505 (IL 75)

QUANTITY SCHEDULES

VERT. SCALE: HORIZ. DATE: 3/3/09

DRAWN BY MTH
CHECKED BY SPF