

# SCHEDULE OF QUANTITIES

PAY ITEM #	DESCRIPTION	UNIT	COMMENTS	PAY ITEM #	DESCRIPTION	UNIT	COMMENTS
63200310	GUARDRAIL REMOVAL	FOOT					
	<u>LOCATION</u>						
	886+27.8 - 887+28.6 LT	100.8					
	885+90.5 - 886+92.7 RT	102.3					
	897+44.1 - 898+45.5 LT	101.5					
	897+12.8 - 898+13.4 RT	100.9					
	709+93.4 - 710+94.4 LT	101.2					
	710+25.9 - 711+26.6 RT	100.8					
	TOTAL =	607.5					
63500105	DELINEATORS	EACH					
	<u>LOCATION</u>						
	886+50.2 LT	1					
	886+50.4 RT	1					
	897+82.3 LT	1					
	897+77.4 RT	1					
	710+38.3 LT	1					
	711+05.6 RT	1					
	TOTAL =	6					
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH					
	<u>LOCATION</u>						
	885+60 50' LT	1					
	885+00 50' LT	1					
	886+25 70' LT	1					
	887+00 70' LT	1					
	888+00 33' LT	1					
	885+76.17 50' RT	1					
	887+00 50' RT	1					
	888+00 33' RT	1					
	896+00 33' LT	1					
	897+00 45' LT	1					
	897+25 70' LT	1					
	898+00 70' LT	1					
	899+00 45' LT	1					
	899+77.17 33' LT	1					
	895+00 33' LT	1					
	896+00 45' RT	1					
	897+00 45' RT	1					
	897+50 65' RT	1					
	898+00 65' RT	1					
	899+00 45' RT	1					
	700+00 33' RT	1					
	709+00 36.45' LT	1					
	710+50 95' LT	1					
	711+00 55' LT	1					
	711+93.23 40' LT	1					
	709+00 33' RT	1					
	710+00 50' RT	1					
	711+25 95' RT	1					
	711+75 95' RT	1					
	712+00 50' RT	1					
	713+00 33' RT	1					
	TOTAL =	31					
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH					
	<u>LOCATION</u>						
	TO BE DETERMINED BY ENGINEER	2					
	TOTAL =	2					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO					
	<u>LOCATION</u>						
	TO BE DETERMINED BY ENGINEER	3					
	TOTAL =	3					
70106700	TEMPORARY RUMBLE STRIPS						
	<u>LOCATION</u>						
	To be placed according to Traffic Control and Protection Standards 701316-03, 701321-09	16					
	TOTAL =	16					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"						
	<u>LOCATION</u>						
	684+41.6 684+86.5 LT (Stage 1)	45.3					
	684+86.5 - 685+416 - 685+79.1 (Stage 1)	93.2					
	684+86.5 - 685+24.5 LT 35' Radius (Stage 1)	48.8					
	685+44.1 - 685+79.1 LT 35' Radius (Stage 1)	54.5					
	685+79.1 - 689+39.7 (Stage 1)	361.3					
	685+65.3 - 685+78.1 RT 20' Radius (Stage 1)	26.2					
	685+78.1 - 687+69.0 RT (Stage 1)	181.2					
	695+17.1 - 700+73.3 (Stage 1)	558					
	696+40.9 - 698+90.4 RT (Stage 1)	249.7					
	708+07.3 - 713+97.6 (Stage 1)	591.9					
	709+40.6 - 712+10.9 RT (Stage 1)	270.4					
	682+56.6 - 685+01.8 (Stage 2)	246.1					
	684+39.4 - 685+18.0 LT (Stage 2)	78.9					
	685+01.8 - 685+50.5 45' Radius (Stage 2)	72.1					
	685+50.0 - 688+83.4 LT (Stage 2)	334					
	685+65.3 - 686+15.0 50' Radius (Stage 2)	77.1					
	686+15.0 - 690+20.3 (Stage 2)	406.3					
	695+42.7 - 700+03.9 LT (Stage 2)	462.2					
	693+61.3 - 701+39.7 (Stage 2)	780.9					
	708+22.1 - 713+34.7 LT (Stage 2)	513.7					
	706+31.7 - 714+69.0 (Stage 2)	704.6					
	TOTAL =	6156.4					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"						
	<u>LOCATION</u>						
	682+46.6 RT	12.1					
	690+80.3 LT	12.1					
	693+51.3 RT	12					
	700+83.3 LT	13					
	706+21.7 RT	12.6					
	715+29.0 LT	12.5					
	TOTAL =	74.3					
70301000	WORKZONE PAVEMENT MARKING REMOVAL						
	<u>LOCATION</u>						
	684+41.6 684+86.5 LT (Stage 1)	45.3					
	684+86.5 - 685+416 - 685+79.1 (Stage 1)	93.2					
	684+86.5 - 685+24.5 LT 35' Radius (Stage 1)	48.8					
	685+44.1 - 685+79.1 LT 35' Radius (Stage 1)	54.5					
	685+79.1 - 689+39.7 (Stage 1)	361.3					
	685+65.3 - 685+78.1 RT 20' Radius (Stage 1)	26.2					
	685+78.1 - 687+69.0 RT (Stage 1)	181.2					
	695+17.1 - 700+73.3 (Stage 1)	558					
	696+40.9 - 698+90.4 RT (Stage 1)	249.7					
	708+07.3 - 713+97.6 (Stage 1)	591.9					
	709+40.6 - 712+10.9 RT (Stage 1)	270.4					
	682+56.6 - 685+01.8 (Stage 2)	246.1					
	684+39.4 - 685+18.0 LT (Stage 2)	78.9					
	685+01.8 - 685+50.5 45' Radius (Stage 2)	72.1					
	685+50.0 - 688+83.4 LT (Stage 2)	334					
	685+65.3 - 686+15.0 50' Radius (Stage 2)	77.1					
	686+15.0 - 690+20.3 (Stage 2)	406.3					
	695+42.7 - 700+03.9 LT (Stage 2)	462.2					
	693+61.3 - 701+39.7 (Stage 2)	780.9					
	708+22.1 - 713+34.7 LT (Stage 2)	513.7					
	706+31.7 - 714+69.0 (Stage 2)	704.6					
	TOTAL =	6156.4					
70400100	TEMPORARY CONCRETE BARRIER						
	<u>LOCATION</u>						
	686+07.5 - 687.69.9 (Stage 1)	162.5					
	687+86.2 - 688+10.9 (Stage 2)	125					
	698+04 - 700+28.4 (Stage 2)	225					
	TOTAL =	512.5					
70400200	RELOCATE TEMPORARY CONCRETE BARRIER						
	<u>LOCATION</u>						
	(686+07.5 - 687.69.9) TO (686+24.0 - 687+86.2) (Stage 2)	162.5					
	(686+24.0 - 688+10.9) TO (696+23.7 - 696+10.8)	287.5					
	(696+23.7 - 699+10.8) TO (695+17.1 - 696+04)	287.5					
	(695+17.1 - 697+04.1) TO (709+19.7 - 711+07.0)	187.5					
	(697+04.1 - 699+78.6) TO STORAGE	275					
	(709+19.7 - 711+07.0) TO (708+94.8 - 710+42.0) (Stage 2)	187.5					
	STORAGE TO (710+42.0 - 713+56.4) (Stage 2)	275					
	TOTAL =	1662.5					