

SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE:

SFTY-2A

CODE NO.	ITEM	UNIT	RURAL 100% STATE TOTAL QUANTITY
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	33
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	58
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	687
50102400	CONCRETE REMOVAL	CU YD	13
50300225	CONCRETE STRUCTURES	CU YD	0.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	12.3
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1940
50800515	BAR SPLICERS	EACH	24
52000110	PREFORMED JOINT STRIP SEAL	FOOT	93
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	687
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	400
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	400
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	800
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	720
78300100	PAVEMENT MARKING REMOVAL	SQ FT	569
X0321468	PLUG EXISTING DECK DRAINS	EACH	20
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	20
X0550300	SLOPE WALL BREAKING	SQ YD	33
50300530	FLOOR DRAIN EXTENSION	EACH	20
Z0016000	DECK SLAB REPAIR (FULL DEPTH)	SQ YD	30
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	70

*** SPECIALTY ITEMS**