

SCHEDULE - CLASS D PATCHING 11"						
LOCATION BY LOG MILE	EBL		WBL		REMARKS	
	TYPE II SQ YD	CUTS FOOT	TYPE II SQ YD	CUTS FOOT		
0.00					PROJECT BEGIN, AT C.L. VINCENNES RD	
0.20	8	36	8	36		
0.22	13	44				
0.23	8	36				
0.25	8	36	8	36		
0.26			8	36		
0.28	8	36	8	36		
0.32	8	36				
0.35	8	36				
0.36			8	36		
0.38	8	36				
0.50						END PROJECT C.L. RTE 17 / 1
TOTALS	69	296	40	180		

SCHEDULE - PAVEMENT MARKING					
LOCATION BY LOG MILE	URETHANE PAVEMENT MARKING LINE 4"		URETHANE PAVEMENT MARKING LINE 6"	REMARKS	
	WHITE	WHITE	YELLOW		
0.00				PROJECT BEGIN, AT C.L. VINCENNES RD	
0.20	6	6	2		
0.22	10		3		
0.23	6		2		
0.25	6	6	2		
0.26		6	2		
0.28	6	6	2		
0.32	6		2		
0.35	6		2		
0.36		6	2		
0.38	6		2		
0.50					END PROJECT C.L. RTE 17 / 1
TOTAL	82		21		

SCHEDULE OF HMA SHOULDER 10"			
LOCATION	EARTH EXCAVATION	HMA SHOULDERS 10"	HMA SURFACE REMOVAL 3"
	CU YD	SQ YD	SQ YD
STA. 114+82 TO STA. 117+96 RT.	29	105	
STA. 117+96 TO STA. 118+59 RT.	4	21	21
STA. 118+59 TO STA. 118+82 RT.	2	8	
TOTAL	36	134	21

FILE NAME =	USER NAME = woodshankr1	DESIGNED - RON WOODSHANK	REVISED - -----
at\pw_work\pwt\dot\woodshankr1\dms91741\0366965-detailed.dgn		DRAWN - RON WOODSHANK	REVISED - -----
PLOT SCALE = 100.0000' / IN.		CHECKED - -----	REVISED - -----
PLOT DATE = Mar 31, 2009 - 01:45:37 PM		DATE - -----	REVISED - -----

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES - FAS 310 (IL 17)

SCALE: _____ SHEET NO. 1 OF 1 SHEETS

*FAI 57, FAS 310

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	D3 PAVEMENT PATCHING 2010-3	KANKAKEE	14	11
ILLINOIS			CONTRACT NO. 66965	