

SUMMARY OF QUANTITIES		URBAN	
CODE NO.	ITEM	CONSTRUCTION CODE: 1000	
		UNIT	TOTAL QUANTITY
20400800	FURNISHED EXCAVATION	CU YD	12
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3259
40600300	AGGREGATE (PRIME COAT)	TON	80
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	6
40600725	POLYMERIZED LEVELING BINDER (HAND METHOD), N50	TON	10
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600990	TEMPORARY RAMP	SQ YD	227
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	79
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1660
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	89
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	769
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	20,297
48101200	AGGREGATE SHOULDERS, TYPE B	TON	625
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2065
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	15,849
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1721
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	689
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15,849
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1721
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	87
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	87
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	825

\* SPECIALTY ITEM

FILE NAME *	USER NAME * schwerkert	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
of:\pwork\PMDDOT\SCHWERTKERT\66973.dwg	66973-dwg-details.dgn	DRAWN -	REVISED -		591	116R05-4	DEKALB	8	3			
PLOT SCALE * 1/8"=1'-0"		CHECKED -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO. 66973	ILLINOIS FED. AID PROJECT	
PLOT DATE * Apr 03, 2001 - 09:00:18 AM		DATE -	REVISED -									